

Tree ID	Common Name	Maturity	Height and direction of first significant branch (m)	Height (m)	No. of Stems	Calculated Stem Diameter (mm)	Radius of Nominal Circle (m)	RPA (m ²)	Crown Spread (m)				Crown Height (m)				Crown	Stem	Basal Area	BS 5837 Category	Life Expectancy	Phys Condition	Comment
									N	E	S	W	N	E	S	W							
T1	Box Elder	Semi-mature	NE 2.5	9	1	420.0	5.0	79.8	3.5	4	3.5	3	2.5	2.5	2	2	Fair	Fair	Fair	C1,2	10 to 20 yrs	Fair	Crown skew due to pruning for road. Past minor pruning to stem and crown. Tag number 0410. Narrow grassy verge, limited room for root growth.
T2	Wild Cherry	Semi-mature	S 3	7.5	1	325.0	3.9	47.8	2.5	3.5	4	4	2.5	2	1.5	2	Fair	Fair	Fair	C1,2	10 to 20 yrs	Fair	Narrow grassy verge, limited room for root growth. Crown skew due to trees north. Past minor to moderate pruning to stem. Minor crown pruning. Tag number 0412.
T3	Sycamore	Young	W 2.5	8.5	1	260.0	3.1	30.6	3	3.5	3	2.5	2.5	4	2	2.5	Fair	Fair	Fair	C2	10 to 20 yrs	Fair	Crown fair to poor. Growing immediately at hard surfacing edge. Two minor deadwood limbs lower eastern crown. Past pruning to stem and crown. Narrow grassy verge, limited room for root growth. Tag number 0414.
T4	Wild Cherry	Young	S 2.5	8	1	270.0	3.2	33.0	3	3	1.5	1	2	2	3	2	Fair	Fair	Fair	C1,2	10 to 20 yrs	Fair	Slight stem lean NE. Located in narrow grassy verge, limited room for root growth. Past minor pruning to stem and crown, mainly lower crown. Pruning wound to stem north at 1.5m, not fully occluded with minor exposed dysfunctional wood. Tag number 0413.
T5#	Lime	Mature	N 4	16	1	600.0	7.2	162.9	3.5	4	4	3.5	2.5	5	4	3.5	Fair	Good	Fair	B1,2	20 to 40 yrs	Fair	Treeline of four lime in similar condition. Limited visual inspection of each, off site behind site security fencing. Past pruning throughout the crown, particularly to lower limbs. Dense shoots at base. Minor deadwood in crown west at approx 8-9m. Dense young growth to lower stem.
T6#	Lime	Semi-mature	N/A	16	1	550.0	6.6	136.8	4	5	3	4	1.5	4	1.5	2	Fair	Fair	Fair	C1,2	10 to 20 yrs	Fair	No dense base epicormic. Light ivy to stem. Reduced crown and quality compared to others. Adjacent construction ongoing in RPAs. Moderate deadwood to centre of the crown, approx 4-6m, three main limbs north east, south east and south.
T7#	Lime	Mature	SW 2	18	1	800.0	9.6	289.5	4	6	5	5	2	5	1.5	3	Good	Good	Fair	B1,2	20 to 40 yrs	Good	Similar to first lime. Construction in adjacent site. Pruning to avoid services west. Multiple bird nests in crown. Dense epicormic at base.
T8#	Lime	Mature	N 2	18	1	650.0	7.8	191.1	5	5	4.5	4.5	3	7	3.5	2.5	Fair	Ivy	Fair	B1,2	20 to 40 yrs	Good	Close proximity to adjacent construction east - potential pruning to facilitate. Construction access road immediately adjacent to east, compaction. Narrow room for root growth. Telephone pole close proximity north west. Pruned to avoid cables. Ivy to stem. Minor deadwood east.
T9	Silver Birch	Young	N 2	5	1	310.0	3.7	43.5	3.5	3	3	3.5	1.5	1.5	1.5	1.5	Poor	Fair	Fair	C2	10 to 20 yrs	Fair	Crown and stem fair to poor due to heavy past pruning. Crown previously topped at approximately 4.5m with resultant moderate deadwood to upper crown. Regrowth and lower crown exhibit good vigour. Considerable pruning to stem with resultant pockets of decay north and east. Central major limb removed with resultant decay, at 2.5m. Fallen deadwood at base. Limited room for root growth.
T10	Field Maple	Young	N/A	5.5	3	240.3	2.9	26.1	3	3	3	3.5	1	0.5	1	1	Fair	Fair	Fair	C2	10 to 20 yrs	Fair	Stem forks at approx 0.8m, three dominant stems alongside low branching. Pruning to lower limbs north east for pedestrian access. Pruned to facilitate adjacent road. Limited room for root growth. Overhead services.
T11#	Common Ash	Young	SW 3	14	5	384.3	4.6	66.8	6	6	5	6	7	3	2.5	3	Fair	Fair	N/A	C2	10 to 20 yrs	Poor	Minimal foliage in crown. Appears to have undergone significant past works to the crown - potential reduction works, resulting in young crown and multiple deadwood stubs. Base not visible due to boundary fencing. Stems estimated at approx 2.5m height. Pruned to avoid adjacent building and road.
T12#	Leyland Cypress	Semi-mature	N/A	12	1	450.0	5.4	91.6	3	1.5	1	3	2	2	2.5	2	Poor	Fair	Fair	C2	10 to 20 yrs	Fair	Off site behind fencing. Limited visual inspection. Heavy, unsympathetic pruning to the south to avoid overhead services and adjacent road. Resultant void and deadwood in crown.
T13#	Leyland Cypress	Young	N/A	10	1	350.0	4.2	55.4	3	3	1	1.5	5	2	7	8	Poor	Fair	Fair	C2	10 to 20 yrs	Fair	Similar to other, adjacent Leyland. Poor crown due to heavy, unsympathetic pruning, including north.
T14#	Sycamore	Young	E 3	14	1	350.0	4.2	55.4	1.5	4	3	1.5	8	3	3	3	Fair	Fair	Fair	C2	10 to 20 yrs	Fair	Heavy crown skew due to adjacent cypress. Pruning of lower limbs due to adjacent path, road and services. Immediately at fencing. Limited visibility.

417

416

Group ID	Species	BS 5837 Category	Description
H1	Common Beech, Common Holly, Common Ash, Common Lime, <i>Berberis</i> sp., Ornamental sp.	C2	Managed hedgerow in car park of school. Mixed species, predominantly common beech. Height 2m, width varies. Disjunct patch for adjacent telephone pole.