



ANALYTICAL TEST REPORT

Contract no: 113804

Contract name: Bates - Spalding

Client reference: 3377

Clients name: Castledine Environmental

Clients address: 4 Wymeswold Road
Hoton
Loughborough
LE12 5SN

Samples received: 22 September 2022

Analysis started: 22 September 2022

Analysis completed: 30 September 2022

Report issued: 30 September 2022

Key

U	UKAS accredited test
M	MCERTS & UKAS accredited test
\$	Test carried out by an approved subcontractor
I/S	Insufficient sample to carry out test
N/S	Sample not suitable for testing
NAD	No Asbestos Detected

Approved by:

Abbie Neasham-Bourn
Senior Reporting Administrator

Chemtech Environmental Limited

SAMPLE INFORMATION

MCERTS (Soils):

Soil descriptions are only intended to provide a log of sample matrices with respect to MCERTS validation. They are not intended as full geological descriptions. MCERTS accreditation applies for sand, clay and loam/topsoil, or combinations of these whether these are derived from naturally occurring soils or from made ground, as long as these materials constitute the major part of the sample. Other materials such as concrete, gravel and brick are not accredited if they comprise the major part of the sample.

Lab ref	Sample id	Depth (m)	Sample description	Material removed	% Removed	% Moisture
113804-1	TP01	0.20	Sandy Clayey Loam with Gravel	-	-	9.4
113804-2	TP01	0.60	Sandy Clayey Loam with Gravel	-	-	15.7
113804-3	TP02	0.10	Sandy Clayey Loam with Gravel	-	-	11.5
113804-4	TP02	0.50	Sandy Loamy Clay	-	-	15.5
113804-5	TP03	0.20	Sandy Clayey Loam with Gravel	-	-	7.8
113804-6	TP04	0.40	Sandy Loamy Clay	-	-	16.6

Chemtech Environmental Limited

SOILS

Lab number Sample id Depth (m) Date sampled			113804-1 TP01 0.20 20/09/2022	113804-2 TP01 0.60 20/09/2022	113804-3 TP02 0.10 20/09/2022	113804-4 TP02 0.50 20/09/2022	113804-5 TP03 0.20 20/09/2022	113804-6 TP04 0.40 20/09/2022
Test	Method	Units						
Arsenic (total)	CE127 ^M	mg/kg As	18	11	19	16	18	14
Cadmium (total)	CE127 ^M	mg/kg Cd	0.7	<0.2	0.4	0.5	0.3	0.6
Chromium (total)	CE127 ^M	mg/kg Cr	65	53	70	52	51	81
Chromium (VI)	CE146	mg/kg CrVI	<1	<1	<1	<1	<1	<1
Copper (total)	CE127 ^M	mg/kg Cu	25	14	17	22	21	27
Lead (total)	CE127 ^M	mg/kg Pb	61	74	91	140	74	141
Mercury (total)	CE127 ^M	mg/kg Hg	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5
Nickel (total)	CE127 ^M	mg/kg Ni	28	19	26	19	19	36
Selenium (total)	CE127 ^M	mg/kg Se	1.3	1.1	1.4	1.2	1.2	1.5
Zinc (total)	CE127 ^M	mg/kg Zn	102	83	133	131	79	190
pH	CE004 ^M	units	8.0	8.0	7.7	8.0	8.4	7.9
Phenols (total)	CE078	mg/kg PhOH	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5
Total Organic Carbon (TOC)	CE197	% w/w C	1.3	1.4	2.8	3.5	1.5	3.6
Estimate of OMC (calculated from TOC)	CE197	% w/w	2.2	2.5	4.8	5.9	2.5	6.3
PAH								
Naphthalene	CE087 ^M	mg/kg	<0.02	<0.02	0.06	0.04	0.06	0.02
Acenaphthylene	CE087 ^M	mg/kg	<0.02	0.03	0.13	0.05	<0.02	0.02
Acenaphthene	CE087 ^M	mg/kg	<0.02	<0.02	0.05	<0.02	<0.02	0.03
Fluorene	CE087 ^U	mg/kg	<0.02	<0.02	0.05	<0.02	<0.02	0.02
Phenanthrene	CE087 ^M	mg/kg	0.12	0.35	0.88	0.43	0.10	0.58
Anthracene	CE087 ^U	mg/kg	<0.02	0.04	0.15	0.06	<0.02	0.15
Fluoranthene	CE087 ^M	mg/kg	0.32	0.69	2.16	1.19	0.31	2.10
Pyrene	CE087 ^M	mg/kg	0.28	0.55	1.91	0.98	0.30	2.04
Benzo(a)anthracene	CE087 ^U	mg/kg	0.18	0.33	1.12	0.52	0.18	1.07
Chrysene	CE087 ^M	mg/kg	0.17	0.28	0.86	0.52	0.16	0.85
Benzo(b)fluoranthene	CE087 ^M	mg/kg	0.32	0.43	1.91	0.77	0.37	1.38
Benzo(k)fluoranthene	CE087 ^M	mg/kg	0.09	0.15	0.65	0.24	0.12	0.44
Benzo(a)pyrene	CE087 ^U	mg/kg	0.21	0.28	1.33	0.48	0.23	1.08
Indeno(123cd)pyrene	CE087 ^M	mg/kg	0.24	0.22	1.06	0.44	0.25	0.86
Dibenz(ah)anthracene	CE087 ^M	mg/kg	0.04	0.04	0.20	0.07	0.04	0.13
Benzo(ghi)perylene	CE087 ^M	mg/kg	0.21	0.17	1.00	0.34	0.20	0.68
PAH (total of USEPA 16)	CE087	mg/kg	2.18	3.55	13.5	6.12	2.30	11.5
TPH								
VPH Aromatic (>EC5-EC7)	CE067	mg/kg	<0.01	-	-	-	<0.01	<0.01
VPH Aromatic (>EC7-EC8)	CE067	mg/kg	<0.01	-	-	-	<0.01	<0.01
VPH Aromatic (>EC8-EC10)	CE067	mg/kg	<0.01	-	-	-	<0.01	<0.01
EPH Aromatic (>EC10-EC12)	CE250	mg/kg	<1	-	-	-	<1	<1
EPH Aromatic (>EC12-EC16)	CE250	mg/kg	<1	-	-	-	1	<1
EPH Aromatic (>EC16-EC21)	CE250	mg/kg	8	-	-	-	7	3.47
EPH Aromatic (>EC21-EC35)	CE250	mg/kg	178	-	-	-	93	29.16
EPH Aromatic (>EC35-EC44)	CE250	mg/kg	104	-	-	-	69	5.59

Chemtech Environmental Limited

SOILS

Lab number			113804-1	113804-2	113804-3	113804-4	113804-5	113804-6
Sample id			TP01	TP01	TP02	TP02	TP03	TP04
Depth (m)			0.20	0.60	0.10	0.50	0.20	0.40
Date sampled			20/09/2022	20/09/2022	20/09/2022	20/09/2022	20/09/2022	20/09/2022
Test	Method	Units						
VPH Aliphatic (>C5-C6)	CE067	mg/kg	<0.1	-	-	-	<0.1	<0.1
VPH Aliphatic (>C6-C8)	CE067	mg/kg	<0.1	-	-	-	<0.1	<0.1
VPH Aliphatic (>C8-C10)	CE067	mg/kg	<0.1	-	-	-	<0.1	<0.1
EPH Aliphatic (>C10-C12)	CE250	mg/kg	<6	-	-	-	<6	<6
EPH Aliphatic (>C12-C16)	CE250	mg/kg	<6	-	-	-	<6	<6
EPH Aliphatic (>C16-C35)	CE250	mg/kg	314	-	-	-	39	<15
EPH Aliphatic (>C35-C44)	CE250	mg/kg	49	-	-	-	12	<10
Subcontracted analysis								
Asbestos (qualitative)	\$	-	NAD	-	NAD	-	NAD	-

Chemtech Environmental Limited

METHOD DETAILS

METHOD	SOILS	METHOD SUMMARY	SAMPLE	STATUS	LOD	UNITS
CE127	Arsenic (total)	Aqua regia digest, ICP-MS	Dry	M	1	mg/kg As
CE127	Cadmium (total)	Aqua regia digest, ICP-MS	Dry	M	0.2	mg/kg Cd
CE127	Chromium (total)	Aqua regia digest, ICP-MS	Dry	M	1	mg/kg Cr
CE146	Chromium (VI)	Acid extraction, Colorimetry	Dry		1	mg/kg CrVI
CE127	Copper (total)	Aqua regia digest, ICP-MS	Dry	M	1	mg/kg Cu
CE127	Lead (total)	Aqua regia digest, ICP-MS	Dry	M	1	mg/kg Pb
CE127	Mercury (total)	Aqua regia digest, ICP-MS	Dry	M	0.5	mg/kg Hg
CE127	Nickel (total)	Aqua regia digest, ICP-MS	Dry	M	1	mg/kg Ni
CE127	Selenium (total)	Aqua regia digest, ICP-MS	Dry	M	0.3	mg/kg Se
CE127	Zinc (total)	Aqua regia digest, ICP-MS	Dry	M	5	mg/kg Zn
CE004	pH	Based on BS 1377, pH Meter	As received	M	-	units
CE078	Phenols (total)	Extraction, Continuous Flow Colorimetry	As received		0.5	mg/kg PhOH
CE197	Total Organic Carbon (TOC)	Carbon Analyser	Dry		0.1	% w/w C
CE197	Estimate of OMC (calculated from TOC)	Calculation from Total Organic Carbon	Dry		0.1	% w/w
CE087	Naphthalene	Solvent extraction, GC-MS	As received	M	0.02	mg/kg
CE087	Acenaphthylene	Solvent extraction, GC-MS	As received	M	0.02	mg/kg
CE087	Acenaphthene	Solvent extraction, GC-MS	As received	M	0.02	mg/kg
CE087	Fluorene	Solvent extraction, GC-MS	As received	U	0.02	mg/kg
CE087	Phenanthrene	Solvent extraction, GC-MS	As received	M	0.02	mg/kg
CE087	Anthracene	Solvent extraction, GC-MS	As received	U	0.02	mg/kg
CE087	Fluoranthene	Solvent extraction, GC-MS	As received	M	0.02	mg/kg
CE087	Pyrene	Solvent extraction, GC-MS	As received	M	0.02	mg/kg
CE087	Benzo(a)anthracene	Solvent extraction, GC-MS	As received	U	0.02	mg/kg
CE087	Chrysene	Solvent extraction, GC-MS	As received	M	0.03	mg/kg
CE087	Benzo(b)fluoranthene	Solvent extraction, GC-MS	As received	M	0.02	mg/kg
CE087	Benzo(k)fluoranthene	Solvent extraction, GC-MS	As received	M	0.03	mg/kg
CE087	Benzo(a)pyrene	Solvent extraction, GC-MS	As received	U	0.02	mg/kg
CE087	Indeno(123cd)pyrene	Solvent extraction, GC-MS	As received	M	0.02	mg/kg
CE087	Dibenz(ah)anthracene	Solvent extraction, GC-MS	As received	M	0.02	mg/kg
CE087	Benzo(ghi)perylene	Solvent extraction, GC-MS	As received	M	0.02	mg/kg
CE087	PAH (total of USEPA 16)	Solvent extraction, GC-MS	As received		0.34	mg/kg
CE067	VPH Aromatic (>EC5-EC7)	Headspace GC-FID	As received		0.01	mg/kg
CE067	VPH Aromatic (>EC7-EC8)	Headspace GC-FID	As received		0.01	mg/kg
CE067	VPH Aromatic (>EC8-EC10)	Headspace GC-FID	As received		0.01	mg/kg
CE250	EPH Aromatic (>EC10-EC12)	Solvent extraction, GCxGC-FID	As received		1	mg/kg
CE250	EPH Aromatic (>EC12-EC16)	Solvent extraction, GCxGC-FID	As received		1	mg/kg
CE250	EPH Aromatic (>EC16-EC21)	Solvent extraction, GCxGC-FID	As received		1	mg/kg
CE250	EPH Aromatic (>EC21-EC35)	Solvent extraction, GCxGC-FID	As received		1	mg/kg
CE250	EPH Aromatic (>EC35-EC44)	Solvent extraction, GCxGC-FID	As received		1	mg/kg
CE067	VPH Aliphatic (>C5-C6)	Headspace GC-FID	As received		0.1	mg/kg
CE067	VPH Aliphatic (>C6-C8)	Headspace GC-FID	As received		0.1	mg/kg
CE067	VPH Aliphatic (>C8-C10)	Headspace GC-FID	As received		0.1	mg/kg
CE250	EPH Aliphatic (>C10-C12)	Solvent extraction, GCxGC-FID	As received		6	mg/kg
CE250	EPH Aliphatic (>C12-C16)	Solvent extraction, GCxGC-FID	As received		6	mg/kg

Chemtech Environmental Limited

METHOD DETAILS

METHOD	SOILS	METHOD SUMMARY	SAMPLE	STATUS	LOD	UNITS
CE250	EPH Aliphatic (>C16-C35)	Solvent extraction, GCxGC-FID	As received		15	mg/kg
CE250	EPH Aliphatic (>C35-C44)	Solvent extraction, GCxGC-FID	As received		10	mg/kg
\$	Asbestos (qualitative)	HSG 248, Microscopy	Dry	U	-	-

Chemtech Environmental Limited

DEVIATING SAMPLE INFORMATION

Comments

Sample deviation is determined in accordance with the UKAS note "Guidance on Deviating Samples" and based on reference standards and laboratory trials.

For samples identified as deviating, test result(s) may be compromised and may not be representative of the sample at the time of sampling.

Chemtech Environmental Ltd cannot be held responsible for the integrity of sample(s) received if Chemtech Environmental Ltd did not undertake the sampling. Such samples may be deviating.

Key

N	No (not deviating sample)
Y	Yes (deviating sample)
NSD	Sampling date not provided
NST	Sampling time not provided (waters only)
EHT	Sample exceeded holding time(s)
IC	Sample not received in appropriate containers
HP	Headspace present in sample container
NCF	Sample not chemically fixed (where appropriate)
OR	Other (specify)

Lab ref	Sample id	Depth (m)	Deviating	Tests (Reason for deviation)
113804-1	TP01	0.20	N	
113804-2	TP01	0.60	N	
113804-3	TP02	0.10	N	
113804-4	TP02	0.50	N	
113804-5	TP03	0.20	N	
113804-6	TP04	0.40	N	

Chemtech Environmental Limited

ADDITIONAL INFORMATION

Notes

Opinions and interpretations expressed herein are outside the UKAS accreditation scope.

Unless otherwise stated, Chemtech Environmental Ltd was not responsible for sampling.

All testing carried out at Unit 6 Parkhead, Stanley, DH9 7YB, except for subcontracted testing.

Methods, procedures and performance data are available on request.

Results reported herein relate only to the material supplied to the laboratory.

This report shall not be reproduced except in full, without prior written approval.

Samples will be disposed of 4 weeks from initial receipt unless otherwise instructed.

For soils and solids, all results are reported on a dry basis. Samples dried at no more than 30°C in a drying cabinet.

For soils and solids, analytical results are inclusive of stones, where applicable.