

P.C. 6.  LBC

NOTES

SIZING OF TIMBER SECTIONS CAN BE VARIED BY MINOR AMOUNTS TO SUIT TIMBER STOCK.

ANY PROPOSED MAJOR CHANGES MUST BE APPROVED BY CONSERVATION OFFICIAL BEFORE FABRICATION.

WHERE POSSIBLE GLASS STOPS & DOOR STOPS TO BE MACHINED FROM SOLID STOCK.

ALL TIMBER TO BE SELECTED JOINTLY QUALITY SOFT WOOD.

KNOT & PRIME FOR FINAL PAINTING IN-SITU.

GLASS TO BE BEARING IN SUITABLE SILICON COMPOUNDS. BEARING RETAINING FIRE PROOFING GLASS TO BE DOWEL & SCREWED @ RECOMMENDED SPACINGS.

FIXING OF FRAMES & LININGS USING SUITABLE "FISCHER" FIXINGS AND IN ADDITION SUITABLE GUN APPLIED ADHESIVES & EXPANDING FOAM.

ALL DIMENSIONS OF FRAMES, LININGS ETC. MUST BE CHECKED BEFORE MANUFACTURING UNITS.