2 TYPICAL SECTIONS THROUGH CARRIAGEWAY EDGE AND FOOTWAY EDGE

2.1 CHARTS 1, 2, 4 & 5 Type Roads



2.2 CHART 3



2.3 CHART 6



CONSTRUCTION CHART 1

ROADS UP TO 0.25 m.s.a. - NORMAL FLEXIBLE CONSTRUCTION

SUB-GRADE	SUB-BASE (mm) Note 1		SURFACING (mm)		TOTAL THICKNESS REQUIRED (mm)	
Bearing Capacity Class	When sub-grade is classified as Non-Plastic Subgrade	When sub-grade is classified as non-Plastic Subgrade	Base course	Wearing Course	When sub-grade is classified as Non-Plastic Subgrade	When sub-grade is classified as non-Plastic Subgrade
Below 1% & 60% soaked CBR	Note 2	Note 2	Note 2	40	Note 2	Note 2
1%	630 mm	630 mm	110	40	180	180 mm
2%	400	400	110	40	150	150
3%	310	310	110	40	150	150
4%	300	290	110	40	150	175
5%	290	290	110	40	150	190
6-15%	300	150	110	40	150	190
Above 15%						

CONSTRUCTION CHART 2

ROADS UP TO 0.25 m.s.a. - MINIMUM DEPTH FLEXIBLE CONSTRUCTION

(See Clause 5.9.1.8)

SUB-GRADE	SUB-BASE (mm)	SURFACING			TOTAL THICKNESS REQUIRED (mm)	
Bearing Capacity Class	Non-frost susceptible Type 1	Base course		Wearing Course	When sub-grade is classified as non-frost susceptible	When sub-grade is classified as non-frost susceptible
		When sub-grade is classified as frost susceptible	When sub-grade is classified as non-frost susceptible			
Below 1% & 60% soaked CBR	Note 2	200	150	40	Note 2	Note 2
1%	Note 2	200	150	40	Note 2	350
2%	150	200	150	40	340	340
3%	150	200	150	40	340	340
4%	150	200	150	40	340	340
5%	150	200	150	40	340	340
6-15%	150	200	150	40	340	300
Above 15%	150	200	150	40	340	

CONSTRUCTION CHART 3

ROADS UP TO 0.25 m.s.a. - BLOCK PAVER CONSTRUCTION

(See Clause 5.9)

SUB-GRADE	SUB-BASE (mm) Note 1		SURFACING (mm)			TOTAL THICKNESS REQUIRED (mm)	
Bearing Capacity Class	When sub-grade is classified as Non-Plastic Subgrade	When sub-grade is classified as non-Plastic Subgrade	Bedding/Sand (Note 4)	Laying Course	Block Paver	When sub-grade is classified as Non-Plastic Subgrade	When sub-grade is classified as non-Plastic Subgrade
Below 1% & 60% soaked CBR	Note 2	Note 2	50	30	60	Note 2	Note 2
1%	630 mm	630 mm	50	30	60	580	580
2%	400	400	50	30	60	440	440
3%	310	310	50	30	60	445	445
4%	295	295	50	30	60	445	445
5%	295	295	50	30	60	445	380
6-15%	380	200	50	30	60	445	380
Above 15%	295	150	50	30	60	445	

CONSTRUCTION CHART 4

ROADS UP TO 2.0 m.s.a. - NORMAL FLEXIBLE CONSTRUCTION

SUB-GRADE	SUB-BASE (mm) Note 1		SURFACING (mm)		TOTAL THICKNESS REQUIRED (mm)	
Bearing Capacity Class	When sub-grade is classified as Non-Plastic Subgrade	When sub-grade is classified as non-Plastic Subgrade	Base course	Wearing Course	When sub-grade is classified as Non-Plastic Subgrade	When sub-grade is classified as non-Plastic Subgrade
Below 1% & 60% soaked CBR	Note 2	Note 2	180	40	Note 2	Note 2
1%	630 mm	630 mm	180	40	850	850 mm
2%	400	400	180	40	620	620
3%	310	310	180	40	530	530
4%	290	290	180	40	450	450
5%	230	225	180	40	450	445
6-15%	230	200	180	40	450	445
Above 15%	230	150	180	40	450	375

CONSTRUCTION CHART 5

ROADS UP TO 2.0 m.s.a. - MINIMUM DEPTH FLEXIBLE CONSTRUCTION

(See Clause 5.9.1.8)

SUB-GRADE	SUB-BASE (mm) Note 1		SURFACING (mm)		TOTAL THICKNESS REQUIRED (mm)	
Bearing Capacity Class	Non-frost susceptible Type 1		Base course	Wearing Course	When sub-grade is classified as Non-Frost Susceptible	When sub-grade is classified as non-Frost Susceptible
		When sub-grade is classified as frost susceptible	When sub-grade is classified as non-frost susceptible			
Below 1% & 60% soaked CBR	Note 2	260	180	40	Note 2	Note 2
1%	Note 2	260	180	40	850	Note 2
2%	150	260	180	40	620	450
3%	150	230	180	40	530	410
4%	150	230	180	40	450	410
5%	150	210	180	40	450	400
6-15%	150	200	180	40	450	390
Above 15%	150	200	180	40	450	375

CONSTRUCTION CHART 6

ROADS UP TO 2.0 m.s.a. - BLOCK PAVER CONSTRUCTION

SUB-GRADE	SUB BASE (mm) Note 1		SURFACING (mm)			TOTAL THICKNESS REQUIRED (mm)	
Bearing Capacity Class	When sub-grade is classified as Non-Plastic Subgrade	When sub-grade is classified as non-Plastic Subgrade	Bedding/Sand	Laying Course	Block Paver	When sub-grade is classified as Non-Plastic Subgrade	When sub-grade is classified as non-Plastic Subgrade
Below 1% & 60% soaked CBR	Note 2	Note 2	50	30	60	Note 2	Note 2
1%	630 mm	630 mm	50	30	60	580	580
2%	400	400	50	30	60	440	440
3%	310	310	50	30	60	445	445
4%	295	295	50	30	60	445	445
5%	295	295	50	30	60	445	380
6-15%	380	200	50	30	60	445	380
Above 15%	295	150	50	30	60	445	

TYPICAL MANHOLE DETAIL - TYPE A

Depth from ground level to soffit of pipe 3m to 6m



The design of manholes will need to comply with the Undertaker's safety policy

TYPICAL MANHOLE DETAIL - TYPE B

Max depth from ground level to soffit of pipe 3.0m



The design of manholes will need to comply with the Undertaker's safety policy

TYPICAL GULLEY DETAILS



Type G7
Trapped Plastic Road Gulley



Type G5
Trapped Road Gulley

NOT TO SCALE

NOTES:

1) Cover and frame uncoated iron to Clause 5.9.4.
2) Mortar bed & benching to Clause 15.
3) Bricks to be Class B engineering bricks to BS 3921 (single course where necessary to obtain satisfactory fall). Corbelled if required. Frames to be bricked on four sides.
4) Insitu ST3 concrete
5) Position of out let pipe varies in plan
6) Insitu ST3 concrete 150mm thick surround to outlet pipe for first one metre under verge or total length if under carriageway.
7) Where grating is to be trafficked or laid against within 24 hours of frame being placed in position, then a suitable Ultra rapid hardening mortar and concrete (Monoset 241 or similar) shall be used to bed cover and frame.

2.4 CHANNEL BLOCK AND KERB DETAIL





OUTFALL BAY DETAIL FOR DRAINAGE BOARD WATERCOURSE (1:50)

0.50 METRES SERVICE MARGIN DETAIL



TYPICAL MANHOLE DETAIL - TYPE C

Depth from cover level to soffit of pipe 1.0m to 1.5m





Internal dimensions of manhole normally 1240mm x 675mm but manhole walls should be increased for pipes larger than 225mm dia to give 225mm benching each side and the brickwork/masonry units corbelled down to suit cover.

Joint to be as close as possible to face of manhole to permit satisfactory joint and subsequent movement

See specification clause 4.6.6.2 for flexible pipe details





Special Manhole Detail for Stormwater Storage system or Irregular sized pipe connections.



Detail of joint between Bitmac and Block-paved Road (n.t.s.)

NOTE:-

Where sewers have less than 1.2m of cover beneath Carriageway then sewers to be protected with reinforced concrete slabs.



CONCRETE BED & SURROUND

(FOUL DRAINAGE)

2.5 SERVICE MARGIN DETAIL



DESIGNED TO SEWERS FOR ADOPTION - 5th EDITION

Notes.

- All Manhole covers, frames and associated iron work to be aquired from aproved supplier.
- Sub base specification will be determined from site investigation to B.S.5930 (1981) No construction will begin until the investigation report has been accepted by Lincolnshire County Council.
- All iron work to be EN.124, Group 4 (Class D 400) Gully covers to be hinged but not removable. A 600 x 600mm clear opening with a minimum area of waterway of 900 cm² in accordance with the B.S. Manhole covers to be embossed with the Anglian Water logo clearly stating either F.W. or S.W. and to be from an approved supplier

Nominal Size DN	Pipe Bedding Requirement mm
150	10 or 14 nominal single size or 14 to 6 graded
225 to 525	10, 14 or 20 nominal single size or 14 to 6 graded or 20 to 5 graded
600 and above	10, 14, 20 or 40 nominal single size clean well rock or 14 to 6 graded or 20 to 5 graded or 40 to 5 graded

PIPE BEDDING SCHEDULE

Rev F: 19 AUG 2003

1022|03

WITHAM VALLEY CIVIL ENGINEERING LTD.

REDBOURNE HOUSE, CLOSSHILL LANE, WYBERTON, BOSTON, LINCS. PE21 7AA
TEL 01205 311021
FAX 01205 359376

Project

Drawing Type: ENGINEERING DETAILS.

Client: DETERMINED PLAN

Drawing No. E99/ENG.DET./1

Scale: NOT TO SCALE.

Drawn By

Rev