



Block Paved Access Road Construction
(Scale 1:20)

Surface Course:	80mm thick concrete block pavers laid in accordance with the requirements of BS 7533-3. Blocks to be laid in a Herringbone pattern. Colour to be confirmed. Colour to contrast Block Paved Parking Court Construction.
Laying Course:	30mm bedding sand complying with BS 7533-3:2005+A1:2009. The aggregate shall be naturally occurring. Joints and drainage holes to be filled with laying course material.
Binder Course:	110mm thickness of 20mm size recipe mix dense binder course (AC 20 Dense bin 40/60 rec) laid in a single layer or a combination of layers not less than 50mm in thickness not greater than 110mm in thickness. Compaction must be to a void content within the range 2%-8% and all layers must be bonded together. Binder course to be perforated by 75mm cores at 750mm centres.
Geotextile:	1no. layer of geotextile between the the binder course and sub base layer to prevent the movement of fine material.
Sub base:	Minimum 450mm Type 3 sub base compacted to achieve a minimum in-situ CBR value of 30% and / or a minimum stiffness of 35 MPa.
Geomembrane:	Sub base to be wrapped in impermeable geomembrane.




Block Paved Parking Court Construction
(Scale 1:20)

Surface Course:	80mm thick concrete block pavers laid in accordance with the requirements of BS 7533-3. Blocks to be laid in a Herringbone pattern. Colour to be confirmed. Colour to contrast Block Paved Access Road Construction.
Laying Course:	30mm bedding sand complying with BS 7533-3:2005+A1:2009. The aggregate shall be naturally occurring. Joints and drainage holes to be filled with laying course material.
Binder Course:	110mm thickness of 20mm size recipe mix dense binder course (AC 20 Dense bin 40/60 rec) laid in a single layer or a combination of layers not less than 50mm in thickness not greater than 110mm in thickness. Compaction must be to a void content within the range 2%-8% and all layers must be bonded together. Binder course to be perforated by 75mm cores at 750mm centres.
Geotextile:	1no. layer of geotextile between the the binder course and sub base layer to prevent the movement of fine material.
Sub base:	Minimum 450mm Type 3 sub base compacted to achieve a minimum in-situ CBR value of 30% and / or a minimum stiffness of 35 MPa.
Geomembrane:	Sub base to be wrapped in impermeable geomembrane.




Block Paved Driveway Construction
(Scale 1:20)

Surface Course:	60mm thick concrete block pavers laid in accordance with the requirements of BS 7533-3. Blocks to be laid in a Herringbone pattern. Colour to be confirmed.
Laying Course:	30mm laying course to be sand and laid in accordance with BS7533 Part 4 2006.
Sub-Base:	200mm of Type 1 granular material sub-base to SHW Clause 803 and prepared and installed to SHW 802 (assumed CBR value of 5% and over, however, should a lowever value be recorded on site Engineer is to be contacted for alternative specification).




Paving Slab Footpath Construction
(Scale 1:20)


Surface Course:	400mm x 400mm x 38mm thick concrete paving slabs. Colour to be confirmed.
Laying Course:	30mm laying course to be sand and laid in accordance with BS7533 Part 4 2006.
Sub-Base:	100mm of Type 1 granular material sub-base to SHW Clause 803 and prepared and installed to SHW 802 (assumed CBR value of 5% and over, however, should a lowever value be recorded on site Engineer is to be contacted for alternative specification).



50mm x 150mm EF Footway Edging
(Scale 1:10)



127mm x 200mm KL Bullnosed Kerb
(Scale 1:10)



127mm x 125mm KS Bullnosed Kerb
(Scale 1:10)

G30 Consulting Ltd

Copyright © 2016 G30 Consulting Ltd. All rights reserved.

Copying of these plans in full or in part is not permitted unless the written consent of G30 Consulting Ltd is obtained.

General Notes

1. Do not scale this drawing.
2. All dimensions are in millimeters unless stated otherwise.
3. This drawing is to be read in conjunction with all other relevant drawings & specifications.
4. All proprietary items to be installed in strict compliance with manufacturers instructions and recommendations.
5. No works shall commence on site until approval has been obtained from all relevant Agencies / Authorities.
6. All dimensions referred to in this drawing must be verified.

Revision	Description	Date
P1	First Issue	04.06.2018

PRELIMINARY

Unit 6, Neepsend Triangle Business Centre, 1 Burton Road,
Sheffield, South Yorkshire, S3 8BW
W: www.g30consulting.com
E: enquiries@g30consulting.com
T: 0114 349 2720

Project
Proposed Residential Development, Banbury Close, Spalding, Lincolnshire

Title
Construction Details - Sheet 3

Drawn by	Checked by	Paper Size
CB	SG	A1

Drawing Number	Revision	Scale	Date
06-0083-007	P1	As Shown	04.06.2018