






Doors/windows to be double glazed with 12mm air gap. Flat toughened glass to French doors/sidelights, entrance door and internal glazed doors (Part N of Regs).



General Requirements:-
 opening sockets: 12mm x 12mm
 Mablet Rooms: 1/20th floor area 8,000mm²
 Bathroom/Utility/ Kitchen: on opening path 4,000mm²

Provide extractor fans capable of 15litres/sec to Bathroom; 30 1/4 to Utility and 60 1/4 to Kitchen (or each hood capable of 30 1/4).



New extension to have separate balanced fire and fire in Utility. 130 litre cylinder with 50 mm foam insulation. Hot water pipes and storage tank to have adequate thermal insulation.

Hot water and heating systems to have controls to limit the heights of heating periods and the output of the system. Hot water system to be vented.



AMENDED PLAN
 Ref: A1
 SOUTH HOLLAND DC
 HOUSING & PLANNING
 19 MAY 1997
 Ref: 1040/96

Mr. and Mrs. K.T. Davy,
 140, Holbeach Road, SPALDING.
 Extension and Alterations

Written dimensions to be used in preference to scaled, and all measurements to be verified by checking on site.	Scale 1:100
Local Authority Ref. Planning 11/1040/96	Drawing No. 2 A/B
Building Regulations 816/0069/97	Date

A. ROFFE
 BUILDING DESIGN & PLANS
 1, Green Lane,
 SPALDING, Lincs. PE11 2YB
 Tel: 01775-723 680

