



A. PATIO AREAS. To be bounded by low informal hedging and Trellis to define the space whilst allowing views out.
Brett Yorktone slab paving surfacing colour
Natural. 300x600x50 in staggered bond.

B. TERRACES. Selected areas demarcated with Charcoal colour slabs.

C. SCULPTURE GARDEN. Corten steel sculptures to add interest.

D. FORMAL LAWNS. Artificial Turfed areas, graded flat for year-round amenity use.

E. INFORMAL GARDEN AREA. Tree and bulb planting.

F. RAISED TIMBER PLANTERS. Formed with Tanselled Timber Sleepers. 450 high to each end with central two planters 750 high. To contain sensory Herb planting.

- A. PATIO AREAS. To be bounded by low informal hedging and Trellis to define the space whilst allowing views out. Brett Yorktone slab paving staggered colour
Natural. 300x600x50 in staggered bond.
- B. TERRACES. Selected areas demarcated with Charcoal colour slabs.
- C. SCULPTURE GARDEN. Corten steel sculptures to add interest.
- D. FORMAL LAWNS. Artificial Turfed areas, graded flat for year-round amenity use.
- E. INFORMAL GARDEN AREA. Tree and bulb planting.
- F. RAISED TIMBER PLANTERS. Formed with Tanselled Timber Sleepers. 450 high to each end with central two planters 750 high. To contain sensory Herb planting.

Topsoil should generally be a minimum of 400mm depth over planting beds and graded to fall. Imported topsoil to be to BS3882:2007

Herbicide and cultivation: Existing Topsoil is to be treated with selected, non-residual, translocated herbicide prior to planting or screeded to remove unwanted Vegetation, removing from site. All planting areas to then have 50mm depth planting compost spread evenly over surface and worked into top 150mm, with Ericaceous compost added to Rhododendron species, removing all stones greater than 50mm dia. roots and other debris. Ensure subsoil is free-draining, if necessary carrying out ripping to a suitable depth, although avoid areas beneath existing protected trees.

Trees: To be planted in pits 900x900x600mm or dimensions of rootball, whichever is greater, with a addition 25L planting compost.All trees to be underground-guyed. Where planted in grass areas to have 900mm dia. area free of turf and mulched.Native hedge and trees to be rabbit proofed.

Mulch: Immediately following planting, areas are to be watered to field capacity and mulched with 50mm depth pulverised bark.

Grass: All turf/seeded areas to be cultivated to a fine tilth and levelled, removing any stones greater than 25mm dia, together with any other debris. Pre-seeding fertilizer applied at 35gms per m² to ornamental turfed areas. Prior to hand over areas are to be managed to create a uniform and dense sward, free of weeds. All planting areas are to be maintained reasonably free of weed growth and litter, with all dead, dying and otherwise defective plant material to be replaced prior to handover.

Poisonous plants: Please note that we have made every effort to avoid use of poisonous plant materials on the site; however, it should be noted that consumption of any ornamental plant may lead to adverse symptoms.

Nr	Key	Species	Density(nr/m2)
6000	Mar	<i>Narcissus 'Dutch Master'</i>	60

Rev.
B

	Date	Revision	
A 19	12.18	Issued for planning	CD
B 30	11.20	Layout updated. Planting quantities added. CD	