

Planting schedule

Trees							
Number	Abbreviation	Species	Specification	Girth	Height	Common Name	Density
2 No.	AMEBA	Amelanchier 'Ballerina'	Clear Stem 175-200 :C		3.0-3.5m		Counted
1 No.	BETJACA	Betula utilis jacquemontii	Standard :RB	8-10cm		White-barked Himalayan Birch	Counted

Shrubs							
Number	Abbreviation	Species	Specification	Common Name	Height	Pot Size	Density
26 No.	AMELAM	Amelanchier lamarckii			60-80cm	3L	0.7Ctr Double Staggered at 0.7m offset
21 No.	EfEG	Euonymus fortunei 'Emerald Gaiety'	Bushy :C	Euonymus 'Emerald Gaiety'	20-30cm	2L	0.4Ctr
16 No.	LIGOV	Ligustrum ovalifolium	Bushy :C	Green Privet	60-80cm	3L	0.7Ctr
16 No.	LIGAURA	Ligustrum ovalifolium 'Aureum'	Bushy :C	Golden Privet	60-80cm	3L	0.7Ctr
26 No.	PfRR	Photinia fraseri 'Red Robin'	Bushy :C	Christmas Berry 'Red Robin'	60-80cm	3L	0.7Ctr Double Staggered at 0.7m offset
22 No.	POG	Pyracantha 'Orange Glow'	Leader With Laterals :Bushy :C	Firethorn 'Orange Glow'	60-80cm	3L	0.7Ctr Double Staggered at 0.7m offset
10 No.	VIBPRIA	Viburnum tinus 'Eve Price'	Bushy :C	Laurustinus 'Eve Price'	60-80cm	3L	0.6Ctr
67 No.	VIBPRIA	Viburnum tinus 'Eve Price'	Bushy :C	Laurustinus 'Eve Price'	60-80cm	3L	0.6Ctr Double Staggered at 0.5m offset

All plants shall comply with BS 3936, and shall be from a nursery which is a member of the HTA Nursery accreditation scheme.

All shrub beds to receive a minimum of 300mm topsoil to BS3882 Category: multipurpose

Soil beneath topsoil layer to be broken up to a minimum of 200mm before topsoiling takes place.

All grassed areas to receive a minimum of 150mm topsoil to BS 3882

To all planted areas, incorporate a general tree and shrub planting compost to Landscape Architect's approval, to a depth of 75mm.

All trees and shrubs to receive fertiliser, Fisons Ficote slow release 14:14:14 neutral analysis at the following rates:

Trees 250g

Whips/shrubs 25g each

TREE PIT SIZES

Planting pits for standard trees to be depth of root ball, with bottom of pit broken up to a depth of 400mm

Pit sizes:700x700x700 for standard trees

Backfill tree pits with with good quality topsoil mixed with peat free tree planting compost

25 litres per heavy standard tree

Trees to be supported by single stake 1800 long driven into ground by one third. Tree ties to be rubberised attached to stake with galvanised nails.

Shrub beds to be mulched with ornamental grade bark mulch to min. 50mm

Position of all services to be established before any excavations take place

Any trees or shrubs which die within a period of 5 years from the date of planting to be replaced with same size & variety

All open ground whips to receive mesh reinforced tubular rabbit guards in brown, 750mm x 90mmdia., supported by a stake

Turf to be meadow quality turf

KEY

- Proposed tarmac surface
- Block paving and edging
- Paving slabs
- Gravel on heavy duty weed membrane
- New grassed areas-meadow turf
- New planted areas

ANNE EVANS CHARTERED LANDSCAPE ARCHITECT
WAINY ELMS
THE GREEN
SHUSTOKE
COLESHILL
BIRMINGHAM B46 2AN
Tel. 01675 481718
Mobile 07973 671452
email: wainyelms@hotmail.co.uk



DRG.NO. AE1701-01	SCALE 1:200 @A2	TITLE SOFT LANDSCAPE PROPOSALS	SITE WINSOVER ROAD, SPALDING
REV.	DATE April 2017	DRAWN BY AEE	CLIENT OCTAGON DEVELOPMENTS