Allison Homes

Woolram Wygate 7c

LANDSCAPE PROPOSALS

No		Name	Pot	Size	Spacing
Trees					
1	BP	Betula pendula	10L		
2	M	Malus toschonoskii	10L		
3	PS	Crataegus oxyacantha 'Paul's Scarlet'	10L		
Specimen Shrubs					
7	B	Buddleja davidii varr.	5L		
2	C	Cotoneaster comubia	10L		
2	HP	Hydrangea petiolaris	5L		
10	L	Lavatera varr.	3L		
10	P	Phorium tenax	2L		
1	PT	Parthenocissus tricuspidata	2L		
Shrubs in beds					
21	Ca'S'	Cornus alba 'Spaethii'		60-75	750 c/s
31	'OL'	Prunus laurocerasus 'Otto Luyken'		30-45	900 c/s

ESTABLISHMENT NOTES

All trees are to be adequately staked and tied and half a bag of peat free tree and shrub compost incorporated into the backfill for each treehole.

a top dressing of 'Enmag' fertiliser shall be made to all shrub areas and trees following planting strictly in accordance with manufacturer's instructions.

REV A Planting / boundary changes 11/11/98

DETERMINED PLAN

SOUTH HOLLAND DC HOUSING & PLANNING 24 NOV 1998 Ref: 1166/98

DRAWING ISSUED 11 NOV 1998

233 76 1A 1:200 Oct 98

Town & Country Planning
Landscape Architecture
Robert Doughty Consultancy
32 High Street, Helpringham, Sleaford NG34 ORA Tel: (01529) 421646 Fax: (01529) 421358