

HALL PLACE

Stone string-course to
match existing above

lead weathering to top
of pilasters

Painted timber fascia
and cornice with lead
weathering

Fixed Fan Light

Timber framed windows

Glazing Spec:
6mm float Toughened
Safety Glazing throughout

Rendered and painted
masonry stallriser

Replacement timber 6
panel door

New brickwork to be neatly
keyed into existing brick
bond

Extent of damage to
existing stone quoins to be
surveyed post removal of
facade. Care required to
minimise any damage to
the existing stonework
during demolition

Timber glazed and
panelled door

ISSUED

SUPERSEDED

26 AUG 2008

1197/08

REVISION	DATE	DRAWN	CHECKED	DESCRIPTION	SCALE	DATE
CLIENT					1:10	26 Aug 2008
PROJECT					DRAWN	CHECKED
14 Market Place, Spalding		JM				JM
DRAWING TITLE		JOB NUMBER		REVISION		
Shop Front Detail Elevation		231432		101		-