

External Tiles Specification
Encaustic 70x70mm external tiles ENC 15 supplied by Olde English Tel 01992 535981 with 25mm border tile.- classic black and white. 10mm tiles sat on 3mm bed of grey cement based adhesive on 65mm concrete screed on 200mm well compacted hardcore sub base.

924x 2015mm
hardwood door

Ironmongery Spec for BOTH new doors:
Pair Victorian Lever Lock Handles - finish Polished Brass
Victorian Letter Plate 305x 102 - Polished Brass
1 1/2 pairs BS 7352 Hinges
Two number Mortice Door Bolts (top and Bottom) - Polished Brass plate

824x 1981mm
hardwood door

Refer to E Bowman & Sons
1:1 Scale Detail

12.5mm Internal Plaster finish

New Solid wall in Facing Red Brick to
match existing

All hardwood glazing
bead with SS screw
fixings

Refer to E Bowman & Sons
1:1 Scale Detail

Refer to E Bowman & Sons
1:1 Scale Detail

Ex 75x 125mm Frame

Ex 150x125mm Frame

Timber moulded pilaster

Planner
26 NOV 2008
Ref: 1197108

SUPERSEDED

ISSUED

REVISION	DATE	DRAWN	CHECKED	DESCRIPTION	SCALE	DATE
CLIENT	Joy Centre Properties Ltd & Mr M Berwald	1:10	26 Aug 2008			
PROJECT	14 Market Place, Spalding	DRAWN	CHECKED			
DRAWING TITLE	Shop Front Detail	JM	JM			
JOB NUMBER	231432	DRAWING NO.	100	REVISION		