

18	S2	mixed	mature	group of trees along the drive and entrance area in moderate condition, mower/ trimmer damage to stems, suppressed by neighbouring bigger trees, Prunus opposite kitchen is twin-stemmed with included union	no action	
18A	S2	mixed	mature	group of 5 trees in rather poor condition; suppressed, stem damage from trimmers/ mowers, one poor Sorbus east of gate	no action	
19	S4	Fagus sylvatica Beech	mature	specimen tree in moderate condition, but rather poor crown structure, minor deadwood, OHB's to street light, soil compaction	prune back to clear light by approx 2m, spread woodchip from tree work on root plate, and along other trees parallel to fence	3 months
20	S3	Sorbus species	mature	tree in rather poor condition; suppressed and leaning but low risk	no action	
21	S4	Fagus sylvatica Beech	mature	specimen tree in moderate condition, minor deadwood, unusual crown structure, one lower branch to road, soil compaction	check highway clearance of 5-6m in summer 2022	1 year
22	S4	Fagus sylvatica Beech	mature	specimen tree in moderate condition, minor deadwood, some low branches to road, deadwood stubs, soil compaction	check highway clearance of 5-6m in summer 2022	1 year
23	S2	mixed	mature	boundary group of trees, including Birch, Norway maple, to corner of Welland Road, in moderate condition, minor deadwood, OHB's to footpath	check and prune for highway clearance of approx 3m along footpath	3 months
24	S3	Tilia species Lime	mature	group of trees along the boundary in rather poor condition; very poor pruning in past resulting in congested and poor crown structure, minor deadwood, OHB's to footpath, high netting now attached and tangled in the crowns along the playing field side - this will make future tree work difficult, epicormic growth	prune to clear footpath by 3m, remove epicormic growth	3 months
25	S3	Tilia species Lime	mature	tree opposite house no. 112, in moderate condition, minor deadwood, one previous high failure scar has woodpecker nest hole, OHB's to highway, epicormic growth	prune back OHB's to clear highway to approx 5-6m, remove epicormic growth to 3m, leave the woodpecker nest site in deadwood scar	3 months
26	S4	Tilia species Lime	mature	group of 12 trees along the boundary in moderate condition, with typical Lime minor deadwood, OHB's to highway (bus parking) and cricket nets, epicormic growth	prune back OHB's to clear highway to approx 5-6m - remove at main stem where appropriate, remove epicormic growth to 3m	3 months
27	S2	mixed	mature	group of 3 trees in moderate condition, stem damage	no action	
27A	S3	Acer platanoides Norway maple	mature	tree appears to be in moderate condition; included union at 2.5m, minor deadwood, some low branches to footpath and bus parking area	prune back OHB's to fence line to clear highway, prune to clear cricket net	3 months
28	S3	Prunus species	mature	tree on the boundary, appears to be in moderate condition; poor pruning in past and wound development, one stem has area of decay at 2m leading to neighbouring school, some low target deadwood, OHB's to neighbour	remove one branch see photo below	3 months
29	S2	Prunus species	mature	tree in rather poor condition; suppressed, soil compaction, poor pruning in past, some materials/ rubbish on root plate, OHB's to neighbour not actionable	remove materials from root plate if possible	6 months
30	S4	Aesculus hippocastanum Horse chestnut	mature	significant tree near the boundary, in moderate condition, stem now clear of ivy and debris, still some leaf litter around stem, high OHB's to neighbour and close to school building	prune crown back from school building by 2-3m, remove approx 60cm of litter from brick wall side of stem	3 months
31	S2	Prunus subhirtella	mature	tree in rather poor condition; poor pruning and structure but some interest and low risk, suppressed by scrub in border - ivy, rose, bramble etc	suggest remove scrub from building and tree to open up	3 months
32	S2	Fagus sylvatica Dawyck	semi mature	tree in moderate condition	no action	
33	S3	Prunus padus	mature	tree in planting pit in rather poor condition; has been poorly pruned and had root damage from construction work in past, stressed - epicormic growth, OHB's to school building and neighbour, soil compaction	pollard at approx 5-6m, remove lower branches and epicormic growth to clear neighbour and cycle shed	3 months
34	S2	Betula pendula Birch	mature	2 trees growing in compacted planting pit, in moderate condition, minor deadwood	spread woodchip from tree work on root plates	3 months
34A	S2	Fraxinus excelsior Ash	mature	neighbours unmanaged tree and ivy growing over school mobile	cut all back to wall line to clear mobile	3 months