WINDOW & LINTEL SCHEDULE

WINDOW NO	LOCATION	SIZE OF OPENING W x H	LINTEL TYPE & LENGTH	WINDOW TYPE	GLAZING	TRICKLE VENT	DECORATION	OTHER
W1	ANNEX BED 8	WIDTH TO MATCH THAT ON PART FIG 2 APPROX 1335 DEPTH AS EXISTING APPROX 1500	1 NO 1.6 100 HD BOX x 1650 LONG 1 NO 1.6 200 HD BOX x 1650 LONG	TO MATCH THOSE ON PART FLANK. FOR PURPOSE OF TENDER ASSUME 2 NO SELD WEN LEW115V	6-16-6 SEALED DOUBLE GLAZED UNITS WITH LOW E OR TOUGHENED GLASS TO BOTTOM PANES	2 x 6000 mm²	WHITE GLOSS	CONCRETE CILL & DECORATE AS EXISTING WITH MASONRY PAINT
W2	ANNEX BED 9	1200 x 1500	1.6 L/S x	SELD WEN LEW2 1ST X OAK HAND	DITTO	8000 mm²	DITTO	DITTO
W3	ANNEX BED 14	1200 x 1500	1.6 L/S x	SELD WEN LEW2 1ST X OAK HAND	DITTO	8000 mm²	DITTO	DITTO
W4	ANNEX BED 14	1200 x 1500	1.6 L/S x	SELD WEN LEW2 1ST X	DITTO	8000 mm²	DITTO	DITTO
W5	ANNEX LANDING 2ND FLOOR	1145 x 2100	N/A STUD	PURPOSE MADE TO MATCH STYLE OF DOOR D45	4-6-4 TOUGHENED DOUBLE GLAZING WITH LOW E COATING OF	8000 mm²	DITTO	
W6	ANNEX BED 15	630 x 1500	N/A STUD	SELD WEN LEW2 1 1ST	4-16-4 SEALED DOUBLE GLAZED UNITS WITH LOW E OF TOUGHENED GLASS TO BOTTOM PANELS	4000 mm²	DITTO	
W7	ANNEX BED 16	1200 x 1500	N/A STUD	SELD WEN LEW2 1ST X	DITTO	8000 mm²	DITTO	
W8	ANNEX BED 16	1200 x 1500	N/A STUD	SELD WEN LEW2 1ST X	DITTO	8000 mm²	DITTO	
W9	ANNEX BED 17	1200 x 1500	N/A STUD	SELD WEN LEW2 1ST X	DITTO	8000 mm²	DITTO	
W10	ANNEX BED 17 EN SUITE	1200 x 1500	N/A STUD	SELD WEN LEW2 1ST X	DITTO	8000 mm²	DITTO	
W11	ANNEX BED 18	1200 x 1500	N/A STUD	SELD WEN LEW2 1ST X	DITTO	8000 mm²	DITTO	
W12	ANNEX BED 18	1200 x 1500	N/A STUD	SELD WEN LEW2 1ST X	DITTO	8000 mm²	DITTO	
W13	CLEY HALL DINING ROOM	SEE PLAN & ELEVATIONS		PURPOSE MADE SOFTWOOD STYLE & DETAILS TO MATCH EXISTING BAY	SINGLE GLAZING LAMINATED TO BOTTOM PANES, FLOAT TO TOP PANES	NONE	TO MATCH EXISTING DECORATION	CLOSE/FALSE TEMPERED CONCRETE & DECORATE TO MATCH EXISTING
W14	CLEY HALL REAR LOBBY	SEE PLAN & ELEVATIONS	N/A STUD	PURPOSE MADE SOFTWOOD	DITTO	NONE	DITTO	
W15	CLEY HALL REAR LOBBY	SEE PLAN & ELEVATIONS	N/A STUD	PURPOSE MADE SOFTWOOD	DITTO	NONE	DITTO	

SHDC
PLANNING & DEVELOPMENT
24 NOV 2003
Ref: 1422/03

DETERMINED

Contractor To Check All Dimensions On Site Before Work Commences.

Rev.	Date.	Init.	Revision Details.

PODDINGTONS
Architectural Design Consultants
Unit 7, The Flaxmill, Flaxmill Lane, Pinchbeck, Spalding, Lincs. PE11 3XQ.
Tel: 01775 720866 Fax: 01775 720877

Project.
MR & MRS G MOWAT
CLEY HALL HOTEL
22 HIGH STREET SPALDING

Drawing. WINDOW & LINTEL SCHEDULE

Scale.

Drawing. No. 3130 - 11

Drawn.

Date. NOV 2003

Rev.