BUILD UP GABLES TO FRONT OF ANNEX WITH BRICKS, BOND & MORTAR TO MATCH EXISTING

LINE OF EXISTING PARAPET & CHIMNEY

W7 W8 W9 W10 W11 W12

W4 W3 W2

W1

D33 D34 D35 D36 D6

MAXIMUM 7250

MAXIMUM 5800

EXTENSION TO EASTERN END OF ANNEX BRICKS, BOND & MORTAR TO MATCH EXISTING

EXISTING TIMBER WINDOW

ALL EXTERNAL DOORS TO ANNEX EXCEPT HARDWOOD DOORS ON NORTH WEST ELEVATION TO BE PAINTED WITH DULUX HERITAGE RANGE MID GROENWICK GREEN. FRAMES WHITE (OWN COLOUR NO 85 REFERENCE)

WINDOWS TO ANNEX TO BE PAINTED WHITE AS EXISTING

EXTERNAL WALLS PREVIOUSLY PAINTED PINK TO BE PAINTED WITH DULUX MASONRY PAINT ONE WHITE GRAMERCYMAR FIX 6014 83/094 QS REFERENCE NO 321

RAINWATER & SOIL GOODS TO BE BLACK AS EXISTING

SOUTH WEST ELEVATION

NORTH EAST ELEVATION

SHDC
PLANNING & DEVELOPMENT
24 NOV 2003
Ref. 1422/03

DETERMINED
PLAN

Contractor To Cheok All Dimensions On Site Before Work Commences.

Rev.	Date.	Init.	Revision Details.
A	9-10-3	AB	ALTER TO SUIT PLANNING COMMENTS
B	12-11-3	AB	PLANNING APPLICATION

PODDINGTONS
Architectural Design Consultants
Unit 7, The Flaxmill, Flaxmill Lane, Pinchbeck,
Spalding, Lincs. PE11 3XQ.
Tel: 01775 720866 Fax: 01775 720877

Project.
MR & MRS G. MOWAT.
CLEY HALL HOTEL.
22, HIGH STREET, SPALDING.

Drawing.
NE & SW ELEVATIONS AS PROPOSED

Scale.	Drawing. No.
1:50	3102 - 7
Drawn.	
Date. JUNE 2003	Rev. A B