NEW SECTION OF MACADAM FOOT PATH
TACTILE PAVING
EXISTING LANDSCAPING
EXISTING MACADAM FOOT PATH
EXISTING LANDSCAPING
TRANSITION KERB
DROP KERB
TROLLEY PARK
99.500
99.475
WHITE LINING
WHITE 'LINING'
EXISTING MACADAM CAR PARK AREA
BOUNDARY
EXISTING MACADAM CAR PARK AREA
TRANSITION KERB
BLOCK PAVED FOOTPATH
CANOPY OVER
11 N° RAM RAID BOLLARDS
BLOCK PAVED (HERRINGBONE AS EXISTING)
1 IN 20
7 N° BOLLARDS
CANOPY OVER
99.525
99.350
99.475
MAIN ENTRANCE
99.650
99.500
RWP
TACTILE PAVING
WINFREY AVENUE
BOUNDARY
REPLACE RAIL AND FENCE
EXISTING MACADAM FOOT PATH
EXISTING LANDSCAPING
REMOVE PETROL TANK AREA
SALES
FFL 99.650
RETAIL UNIT
FFL 99.650
INTERNAL FITOUT BY TENANT
DRAIN PROVIDED
INTERNAL FITOUT BY TENANT
DRAIN PROVIDED
ELECTRIC
GAS
WATER
ELECTRIC GAS WATER
2 N° BOLLARDS
NEW CHANNEL
2 N° BOLLARDS
2 N° BOLLARDS
SEALED SKIP STORAGE AREA
2 N° BOLLARDS
SEALED SKIP STORAGE AREA
99.450
99.575
99.650
99.850
99.725
RAMP UP
100.000
CONDENSATE WASTE
LOW WALL
BLOCK PAVED FOOT PATH
FFL 100.000
PLANT ENCLOSURE
LANDSCAPING
BLOCK PAVED FOOTPATH
EXIST POST & RAIL FENCE
NEW CHANNEL EXTENSION
EXISTING CHANNEL
100.00
MACADAM FOOT PATH
ENLARGE EXISTING VEHICLE CROSSING
TACTILE PAVING
BOUNDARY
ENLARGE EXISTING VEHICLE CROSSING
TACTILE PAVING
NEW SECTION OF MACADAM FOOT PATH
TACTILE PAVING
SWAN STREET
REPAIR 3m OF EXIST POST & RAIL FENCE
REFURBISHED PLANTING
EXISTING FOOTPATH
BOUNDARY

22m². Shrubs 3/m² = 66no.
(a) 22. Berberis darwinii
(b) 22 Cotoneaster franchettii
(c) 22. Hypericum hidcote
Mulch of forest bark.

9m². Shrubs 3/m² = 27no
27. Escallonia C.F. Ball
Mulch of forest bark.

12m². Shrubs 3/m² = 36no.
(a) 12. Pyracantha mojave
(b) 12 Cotoneaster franchettii
(c) 12. Berberis darwinii mulch with forest bark

9m². Shrubs 3/m² = 27no
(a) 3. Buddleia Black Knight.
(b) 12. Berberis darwinii
(c) 12. Hypericum hidcote . . .

34m². Shrubs 3/m² = 102no.
(a). 20 Berberis darwinii
(b). 20 Hypericum hidcote.
(c). 20 Escallonia Apple Blossom
(d). 20 Pyracantha O. glow
(e) 22 Cotoneaster franchettii
Mulch with forest bark

8m². Shrubs 3/m² = 24no.
(a). 12. Hypericum hidcote
(b). 12. Escallonia Apple Blossom
Mulch with forest bark

KEY

- CONCRETE DELIVERY AREA
- MACADAM CAR PARK AREA
- PAVED FOOT PATH
- MACADAM FOOT PATH
- LANDSCAPE AREA
- +100.000 PROPOSED LEVEL
- DROP KERB
- BOLLARD - GALV. AS 'FOCUS'
- NEW POST & RAIL FENCE
- EXIST POST & RAIL FENCE

THIS DRAWING TO BE READ IN CONJUNCTION WITH DRAWING 001-030-131

Rev. B: Landscaping extended around Plant Enclosure. DB 30.09.04

Rev. A: Tactile paving indicated, notes added. DB 25.06.04

Project title
Supermarket Redevelopment
Winfrey Avenue
Spalding, Lincs

Drawing Title
External Works

Scale 1:100 | Date JAN 2004
Drawn by DB | Checked by

1 NORTH PARK ROAD
HARROGATE
HG1 5PD
TEL 01423 528106
FAX 01423 503648
teamle stoneandmoon.co.uk

11 KING STREET
KNUTSFORD
WA16 6DW
TEL 01565 631450
FAX 01565 631699
knutsfordestoneandmoon.co.uk

STONE & MOON ASSOCIATES
· ARCHITECTURE
· PLANNING
· PROJECT MANAGEMENT

SBDC Planning & Development 20 OCT 2004 Ref: 12/0/04

Drawing no. 001/030/130 | Revision B

A4