



SHDC
Planning & Development
22 DEC 2003
Ref

DETERMINED PLAN

REV. D.

PRIVATE DRIVEWAY LIGHTING POINT + ENERGY SAVING BULB WITH DAY/NIGHT SENSOR.



Sentinel
1 Metre Bollard
Black finish.
Constructed of rust proof die cast aluminium. Polycarbonate panel.
Size: (HxDia.) 1000x235mm.
Lamp: 100W BC GLS or 60W BC Candle.
IP24.
Quote: MM4770

1 : 50 Wall & Fence Details

BUCKS
Planning & Development
23 DEC 2003
Ref 1552/03

LANDSCAPE SCHEDULE

Shrub Specification

1 Vinca Minor
2 Hypericum Calycinum
3 Cotoneaster Skogholm Coral Beauty
4 Cotoneaster Horizontalis
5 Lavenda Spica Hidcote
6 Lonicera Pileata
7 Potentilla Red Ace
8 Senecio Greyii

The above to be planted at 3 per m²

9 Pyracantha Mohave
10 Rosa Rugosa Frau Dagmar Hastrup
11 Viburnum Tinus
12 Hypericum Patulum Hidcote
13 Mahonia Aquifolium

The above to be planted at 2 per m²

14 Greenbeech Fagus Sylvatica – 30cm c/s
15 Parthenocissus tricuspidata – spot climbers


TREES (all standard size)

MT Malus Tchonoskii
CP Crataegus Prunifolia
SA Sorbus Aucuparia
RF Robinia Frisia
m Prunus Avium
AC Acer Campestre
AH Aesculus Hippocastanum

Material Schedule :-

	Plots
Bricks :-	
Marshalls Crowhurst Multi	3, C & 7.
Marshalls Chesnut Multi	1, 2, 4, 5 & 8
Roof Tiles :-	
Sandtoft Terra Cotta Concrete Shire Pantile	1, 2, 4, & 5
Sandtoft light grey Concrete Calderdale Slate.	3 6 7 & 8.

SEE ENGINEERS DRAWINGS FOR FOUL & S.W. DETAILS



1 : 2500 LOCATION PLAN

D FENCE DETAILS AMENDED LIGHTING SCHEME ADDED DEC 03
C Type handing amended on working Drawings Aug 03
Gate to Plot 1 & 6 repositioned Note added
Reference to Fig 6.15 Diagram 6.1 added
B Landscape & Materials Schedule added May 03.
Private road constructed to adoptable standards
A Plot 6 - 292A handed in lieu of 292. Apr 03
Close boarded fence & field gate omitted on Plot 6
Bootop railing in lieu of screen wall to Plots 7 & 8

© This drawing is copyright.
Contractors must check all dimensions on Site. Only figured dimensions are to be worked from. Any foundation depths indicated are indicative only and must be in accordance with the consulting engineers design and/or agreed on Site with the local authority during excavations. Any discrepancies in the information contained herein must be reported to the Architect before work proceeds.

Project
PROPOSED RESIDENTIAL DEVELOPMENT AT 161 WINSOVER ROAD SPALDING LINCS

Drwg. SITE & LOCATION PLANS

Scale 1 : 200 & 1 : 2500 | Date MAR 03

Drwg. no. 21239/01 | Rev. C D

architects · designers · planning consultants
Old School House · 36 Boston Road · Sleaford
Lincolnshire · NG34 7EZ · Tel: 01529 414141
Fax: 01529 415757

clive wicks associates

©