

Appendix 1 – Discharge of conditions – H17-1152-19

Condition 3 –

Geo Environmental Risk Assessment Reports already submitted to you by previous owner.
Reports prepared by Delta Simons August 2019

Tank Removal and Validation Report prepared by Delta Simons and submitted to you April 2020 copies also attached to this application.

Remediation Method Statement prepared by Delta Simons and also submitted to you in April 2020 with the above report and also attached to this application.

Condition 6 –

Cross Sectional details of doors – drawing attached. Lintol details as per plans submitted and passed by SHDC.

Condition 7 –

Cross Sectional details of windows – drawing attached. Lintol details as per plans submitted and passed by SHDC.

Condition 8 –

Wherever possible all bricks are to be used from site, i.e from new openings that are being created. Bricks are being cleaned and reused. Some reclaimed bricks have been purchased and are a very good match (from another local barn).

Mortar – A lime mortar is being used 1:2:9 Bond – there are several different bonds used on the original building and we are copying the bond surrounding the brickwork being replaced.

Condition 10 –

Finished floor levels have been set at 3.920 OD as per plans submitted and passed by SHDC, 0.57 above minimum requirements.