ADD Level = Level shown - 46.575

ALL SOIL VENT PIPES AND RAINWATER PIPES ARE INDICATIVE ONLY. TO BE CONFIRMED ON SITE.

THE SIZE FOR HOOFTANK IS BASED ON ASSUMED SOAKAGE OF 1×10^{-5} M³ /S. CONTRACTOR TO CARRYOUT SOAKAGE TEST ON SITE PRIOR TO ANY CONSTRUCTION.

EXISTING SERVICES AT PROPOSED ENTRANCE TO SITE MAY REQUIRE LOWERING. CO-ORDINATION WILL BE REQUIRED FOR ANY POSSIBLE CLASHES.

REMOVE EXISTING TREE

EXISTING 150ø MAIN

EXISTING 150ø MAIN

EXIST. FMH AWS REF 2201 CL49.94 IL47.03

BD IL 47.65

SW5 CL49.95 IL49.28

RE4 CL49.95 IL49.50

slow radius bend

F1 CL49.95 IL49.20

F2 CL49.95 IL49.10

SW1 CL49.95 IL49.34

F8 CL49.91 IL47.98

SW6 CL49.85 IL49.19 (CATCHPIT)

F6 CL49.85 IL48.23

RE3 CL49.95 IL49.50

SW4 CL49.95 IL49.28

SW2 CL49.95 IL49.42

F4 CL49.95 IL48.65

RE2 CL49.95 IL49.50

F5 CL49.95 IL48.50

SW3 CL49.95 IL49.09 CATCHPIT

F3 CL49.95 IL48.86

Hoofmark 400 Deep 31.5 CU.M Storage Area 2

Hoofmark 400 Deep 18 CU.M Storage Area 1

FFL 50.100

STORE
ADMINISTRATION / RECORDS
DISPENSARY
INTERVIEW ROOM
RECEPTION
WAITING AREA
LIFT MOTOR
STAIR 01
NURSE
CONSULTING ROOM 06
CONSULTING ROOM 05
CORRIDOR
TREATMENT ROOM 01
TREATMENT ROOM 02
UTILITY
UTILITY ROOM
W.C.
CONSULTING ROOM 04
DIS W.C.
RECEPTION / OFFICE
MULTI PURPOSE
CONSULTING ROOM 1 MULTI PURPOSE
CONSULTING ROOM 02
CONSULTING ROOM 03
HEALTH PROMOTION
STORE
CORRIDOR
PODIATRY
STORE
SPEECH THERAPY
BOILER
CONSULTING / ASSESMENT
VIEWING / OFFICE / INTERVIEW
STORE

RAILWAY LANE

SHDC Planning & Development 24 FEB 2005 Ref: 0239/05

DETERMINED PLAN

NOTES

1. THIS DRAWING TO BE READ IN CONJUNCTION WITH SPECIFICATIONS AND ALL OTHER RELEVANT DRAWINGS
2. ALL PRIVATE DRAINAGE SHALL BE CARRIED OUT IN ACCORDANCE WITH PART H OF THE CURRENT BUILDING REGULATIONS.
3. ALL COVER LEVELS SHOWN ON THIS DRAWING ARE APPROXIMATE. EXACT LEVELS TO BE DETERMINED ON SITE TO SUIT ADJACENT FINISHED GROUND LEVELS.
4. NO DRAINAGE FROM PRIVATE AREAS TO BE DISCHARGED TO PUBLIC HIGHWAY. DRIVES TO BE LAID TO FALL TO GULLYS AT LOW POINTS TO ENSURE COMPLIANCE.
5. NO GATES, ETC TO OPEN OVER THE PUBLIC HIGHWAY OR FOOTPATH.
6. FOR PROPOSED FINISHES REFER TO ARCHITECTS DRAWINGS.
7. FOR PRIVATE DRAINAGE DETAILS REFER TO DRAWING NO. 271003/03 AND 04.
8. THE STORM AND FOUL DRAINAGE IS DESIGNED TO SURVEY CARRIED OUT REF. DRAWING No. 271003/01 AND ANGLIAN WATER SEWERS RECORDS. CONTRACTOR TO VERIFY COVER LEVELS AND INVERT LEVELS OF OUTFALL MANHOLES PRIOR TO ANY CONSTRUCTION ON SITE.
9. ALL SVP PIPES TO BE 100ø @ 1:40 MIN. UNLESS NOTED OTHERWISE.
10. ALL RAINWATER PIPES TO BE 100ø AT 1:100 MINIMUM FALL UNLESS NOTED OTHERWISE.
10. LEVELS SHOWN AS × THUS REQUIRE TO BE VERIFIED ON SITE PRIOR TO ANY WORKS.
12. ALL ADOPTABLE DRAINAGE TO BE CARRIED OUT TO THE LATEST ADOPTABLE STANDARDS AND APPROVED BY THE AUTHORITIES.
13. FOR ADOPTABLE DETAILS AND SECTIONS REFER TO DRAWING No. 271003/05

LEGEND

- PIPE ø/GRADIENT (100/100)
- PROPOSED S.W. SEWER
- PROPOSED FOUL SEWER
- R.W.P.
- RODDING EYE
- SVP SOIL VENT PIPE SS SUB STACK
- PRIVATE FOUL MANHOLE
- PRIVATE STORM MANHOLE
- EXISTING F.W. MANHOLE (adoptable) (EXISTING 150ø)
- PROPOSED F.W. MANHOLE (adoptable) (150/150)
- big Back Inlet Gully

REV	DATE	REMARKS
A	15/01/04	Drawing Re-numbered & Issued 'For Construction'.

STATUS FOR CONSTRUCTION

SIDEBOTTOM RICHARDSON CHENG LTD
15 HIGH STREET, SPALDING, LINCS. PE11 1TW
TEL: (01775) 712660 FAX: (01775) 712635
CONSULTING STRUCTURAL AND CIVIL ENGINEERS E-MAIL: srcltd-r-c.co.uk

PROJECT
Proposed Medical Centre
Sutton Bridge
Lincolnshire

TITLE
Drainage Layout

DATE	OCT-03	SCALE	1:200 / / -
DRAWN	SRC	CHECKED	
DESIGN		FILENAME	29403-10-13

DRG No. 29403/10 REV A