Avenue Farm

Ⓑ-Ⓒ-Ⓓ DISMANTLE LV LINE.

25KVA 1Ø
MD 1995/96 = 12KVA

120 ALPEX

3x50 A.C.S.R.

Nº 217
AVENUE FARM
PROPOSED
100KVA 3Ø PMT.
EST. MD. 1996/97 = 90KVA.

Nº 183
THE AVENUE

Ⓔ-Ⓕ REPLACE PVC. A.C.S.R.
WITH 3x50 A.C.S.R.
BT TO INSULATE U/G SERVICE.

ADD STAY

Ⓐ-Ⓑ DISMANTLE HV LINE.

ADD STAYS AND TERMINATE HV LINE.

SEE WAYLEAVE OFFICER BEFORE STARTING.

H18/0677/96

SOUTH HOLLAND DISTRICT COUNCIL
PLANNING
22 JUL 1996
Ref: H677/96

East Midlands Electricity

EAST LINCOLNSHIRE DISTRICT

Title AVENUE FARM, SUTTON BRIDGE.

	EXISTING	PROPOSED	TO BE DISMANTLED
Overhead Lines Shown	33 kv, 11 kv, LV		
Underground Cables Shown	33 kv, 11 kv, LV		
Transformers Shown	G.M.T., P.M.T.		

Grid Sheet No. T.F. 4623/4 | Scale 1:2500 | Drawn K.B.

Based upon the Ordnance Survey with the sanction of the Controller of H.M. Stationery Office
CROWN COPYRIGHT RESERVED.

Scheme No. 97888.
Dwg. No. 96/97888
Date 11-7-96