

Porter, Karen

From: noreply@salesforce.com on behalf of National Gas Asset Protection <box.assetprotection@nationalgas.com>
Sent: 29 October 2025 10:14
To: _planningadvice
Subject: Objection - National Gas Transmission -LSBUD Reference Number: GE2_39059073-H18-0953-25
Attachments: Objection - National Gas Transmission - LSBUD Reference Number - GE2_39059073-29_10_2025 10_11.pdf

Caution: This message originated from outside of the organisation. Do not click links or open attachments unless you recognise the sender and know the content is safe. If you believe it is suspicious please forward to Suspicious.Emails@pspsl.co.uk and delete the email.

Hi Planning,

Please see below Holding Objection.

Holding Objection:

National Gas Transmission operates a high-pressure gas pipeline - FEEDER 7 - HOLBEACH BANK TO SUTTON BRIDGE in the vicinity of the proposed development.

The pipeline has an easement in operation. No development, construction or landscaping is permitted within the easement without formal written approval from National Gas Transmission.

The pipeline has a 81m 'Building Proximity Distance' (BPD), which restricts development within this distance. Further guidance for consultation zones around a Major Hazard Pipeline can be found at:

<https://www.hse.gov.uk/landuseplanning>

It is the Local Authority & Developer's responsibility to ensure that the requirements of LUP are adhered to.

The proposed development appears to fall outside the easement and BPD but within 4X BPD corridor.

Industry and Company standards place a limit on the number of dwellings within the 4 x BPD corridor, which may require risk assessment before planning permission is granted. This is to ensure the risk to population is within NGT's risk criterion envelope as described in these standards.

The HSE are a statutory consultee and must be approached for comment when assessing any planning application and the formation of a population cluster and/or increased population density near the pipeline as a result of the development in the vicinity of a high pressure gas pipeline.

Please ask the developer to submit the response from the HSE.

The holding objection will remain in place until the HSE response has been received.

[This content is a preview of a link. www.hse.gov.uk](https://www.hse.gov.uk/landuseplanning)

www.hse.gov.uk

<https://www.hse.gov.uk/landuseplanning>

Kind regards

Jordane Maples

Asset Protection Assistant

Asset Protection

07702622482

Jordane.maples@nationalgas.com



National Gas Transmission, Warwick Technology Park, Gallows Hill, Warwick, CV34 6DA

nationalgas.com | [Twitter](#) | [LinkedIn](#)

Please consider the environment before printing this email.

Planning Sevenoaks District Council

Jordane Maples
Asset Protection
Direct Tel: 07702622482
Email: jordane.maples@nationalgas.com

Planning Work?
Please enquire with us at
www.lsbud.co.uk

National Gas Emergency Number:
0800 111 999*

*Available 24 hours, 7 days/week.
Calls may be recorded and monitored.
www.nationalgas.com

Date: October 29, 2025

Our Reference: GE2_39059073

Your Reference: National Gas-H18-0953-25

Dear Planning Sevenoaks District Council,

Ref: Site Address Not Provided

National Gas Transmission exercises its right to place a Holding Objection to the above proposal which will cross our High-Pressure Gas Pipeline – Feeder providing the below conditions are adhered to:
Holding Objection:

National Gas Transmission operates a high-pressure gas pipeline - FEEDER 7 - HOLBEACH BANK TO SUTTON BRIDGE in the vicinity of the proposed development.

The pipeline has an easement in operation. No development, construction or landscaping is permitted within the easement without formal written approval from National Gas Transmission.

The pipeline has a 81m 'Building Proximity Distance' (BPD), which restricts development within this distance. Further guidance for consultation zones around a Major Hazard Pipeline can be found at:
<https://www.hse.gov.uk/landuseplanning>

It is the Local Authority & Developer's responsibility to ensure that the requirements of LUP are adhered to.

The proposed development appears to fall outside the easement and BPD but within 4X BPD corridor. Industry and Company standards place a limit on the number of dwellings within the 4 x BPD corridor, which may require risk assessment before planning permission is granted. This is to ensure the risk to population is within NGT's risk criterion envelope as described in these standards.

The HSE are a statutory consultee and must be approached for comment when assessing any planning application and the formation of a population cluster and/or increased population density near the pipeline as a result of the development in the vicinity of a high pressure gas pipeline.

Please ask the developer to submit the response from the HSE.

The holding objection will remain in place until the HSE response has been received.

This content is a preview of a link.

www.hse.gov.uk

www.hse.gov.uk

<https://www.hse.gov.uk/landuseplanning>

- We would draw your attention to the Planning (Hazardous Substances) Regulations 1992, the Land Use Planning rules and PADHI (Planning Advise for Developments near Hazardous Installations) guidance published by the HSE, which may affect this development.
- To visit the Land Use Planning site, please use the link below:
<https://www.hse.gov.uk/landuseplanning/methodology.htm>
- No buildings should encroach within the Easement strip of the pipeline
- No demolition shall be allowed within 150 metres of a pipeline without an assessment of the vibration levels at the pipeline. Expert advice may need to be sought which can be arranged through National Gas Transmission.
- National Gas Transmission has a Deed of Easement for each pipeline which prevents change to existing ground levels, storage of materials. It also prevents the erection of permanent / temporary buildings, or structures. If necessary National grid will take action to legally enforce the terms of the easement.
- You should be aware of the Health and Safety Executives guidance document HS(G) 47 "Avoiding Danger from Underground Services ", and National Gas Transmission's specification for Safe Working in the Vicinity of National Gas Transmission High Pressure gas pipelines and associated installations - requirements for third parties T/SP/SSW22. You should already have received a link to download a copy of T/SP/SSW/22, from our Plant protection Team, which is also available to download from our website.
- To view the SSW22 Document, please use the link below:
<https://www.nationalgrid.com/uk/gas-transmission/document/113921/download>
- A National Gas Transmission representative will be monitoring the works to comply with SSW22.
- To download a copy of the HSE Guidance HS(G)47, please use the following link:
<http://www.hse.gov.uk/pubns/books/hsg47.htm>
- National Gas Transmission will also need to ensure that our pipelines access is maintained during and after construction.
- Our pipelines are normally buried to a depth cover of 1.1 metres however; actual depth and position must be confirmed on site by trial hole investigation under the supervision of a National Gas Transmission representative. Ground cover above our pipelines should not be reduced or increased.
- If any excavations are planned within 3 metres of National Gas Transmission High Pressure Pipeline or, within 10 metres of an AGI (Above Ground Installation), or if any embankment or dredging works are proposed then the actual position and depth of the pipeline must be established on site in the presence of a National Gas Transmission representative. A safe working method must be agreed prior to any work taking place in order to minimise the risk of damage and ensure the final depth of cover does not affect the integrity of the pipeline.
- Excavation works may take place unsupervised no closer than 3 metres from the pipeline once the actual depth and position has been confirmed on site under the supervision of a National Gas Transmission representative. Similarly, excavation with hand held power tools is not permitted within 1.5 metres from our apparatus and the work is undertaken with NGT supervision and guidance.

Pipeline Crossings

- Where existing roads cannot be used, construction traffic should ONLY cross the pipeline at locations agreed with a National Gas Transmission engineer.
- All crossing points will be fenced on both sides with a post and wire fence and with the fence returned along the easement for a distance of 6 metres.
- The pipeline shall be protected, at the crossing points, by temporary rafts constructed at ground level. No protective measures including the installation of concrete slab protection shall be installed over or near to the National Gas Transmission pipeline without the prior permission of National Gas Transmission. National Gas Transmission will need to agree the material, the dimensions and method of installation of the proposed protective measure. The method of installation shall be confirmed through the submission of a formal written method statement from the contractor to National Gas Transmission.
- Please be aware that written permission from National Gas Transmission is required before any works commence within the National Gas Transmission easement strip.
- A National Gas Transmission representative shall monitor any works within close proximity to the pipeline to comply with National Gas Transmission specification T/SP/SSW22.
- A Deed of Indemnity is required for any crossing of the easement including cables

Cables Crossing

- Cables may cross the pipeline at perpendicular angle to the pipeline i.e. 90 degrees.
- A National Gas Transmission representative shall supervise any cable crossing of a pipeline.
- An impact protection slab should be laid between the cable and pipeline if the cable crossing is above the pipeline.
- Where a new service is to cross over the pipeline a clearance distance of 0.6 metres between the crown of the pipeline and underside of the service should be maintained. If this cannot be achieved the service must cross below the pipeline with a clearance distance of 0.6 metres.

All work should be carried out in accordance with British Standards policy

- BS EN 13509:2003 - Cathodic protection measurement techniques
- BS EN 12954:2001 - Cathodic protection of buried or immersed metallic structures – General principles and application for pipelines
- BS 7361 Part 1 - Cathodic Protection Code of Practice for land and marine applications.

I have enclosed a location map to show the location of National Gas Transmission high-pressure gas pipeline(s) within the vicinity of your proposal.

Yours sincerely
Jordane Maples
 Asset Protection Assistant