



Notes:

Road widths 5.5m.
Footpaths 1.8m wide.
Junction radii:-
10m at junction with BRIDGE ROAD and
6m within the internal layout of the site.
Junction Visibility Splays:-
4.5m x 90m at the junction with BRIDGE ROAD and
2.4m x 45m at the junction of ROAD 1 and ROAD 2

This drawing is to be read in conjunction with the
Landscape Architect's drawings

- DO NOT SCALE**
- This drawing is the Copyright protected intellectual property of The Diamond Wood Partnership and is to be used or reproduced in any way without our written permission.
- NOTES
1. This drawing should be read in conjunction with all other Architect's, Engineer's and specialist contractor's details.
 2. The position of all existing drainage apparatus should be verified on site prior to the commencement of the works. Any discrepancies should be reported to the Engineer immediately.
 3. All dimensions are in metres unless otherwise stated.
 4. All works in respect of Public sewerage apparatus shall be subject to the approval of Anglian Water Services Ltd (AWSL).
 5. Surface water drainage shall be subject to the approval of the drainage authority and the Environment Agency.
 6. The highway layout and all highway materials, construction details and workmanship shall be subject to the approval of Lincolnshire County Council or their Agents.

SHDC
Planning & Development
- 8 SEP 2003
Ref

SCHEDULE OF PROPOSED ADOPTED HIGHWAYS			
ROAD	TYPE	WIDTH(m)	SURFACE FINISH
1	MAJOR ACCESS ROAD	5.50	FLEXIBLE - HRA
2	MINOR ACCESS ROAD	5.50	FLEXIBLE - HRA

Ref.	Revision	Date	By
Issue			
PRELIMINARY			
THE DIAMOND WOOD PARTNERSHIP Consulting Engineers			
 The Old School Blaby Road Lincolnshire LE19 4AR T: 0116 254 8989 F: 0116 254 8998 E: mail@diamondwood.co.uk			
Project Title			
PROPOSED DEVELOPMENT BRIDGE ROAD, SUTTON BRIDGE, LINCOLNSHIRE. FOR CANNON KIRK (UK) LTD			
Drawn	MD	Date	08/03
Scale	1:500 @ A1	Checked	
Drawing Title			
PROPOSED ROAD AND DRAINAGE LAYOUT			
Project No.	Drawing No.	Revision	
03/6382	100		