House Ref.	Element			
	Walls	Roof	Joinery / Fittings	Notes
73/T2.3	General wall Areas Red Brown Multi Brickwork, with Red Brick Plinth and Features with Blue Engineering Brickwork below DPC	Slate Grey Redland Stonewold II interlocking Concrete Roof Tiles	All Windows to be In White Finished UVPC Entrance Portico Detail to front Elevation to be in White GRP by Specialist	
74/T2.4	General wall Areas Buff Multi Brickwork, with Red Brick Features and Blue Engineering Brickwork below DPC	Red/Brown Redland Stonewold II interlocking Concrete Roof Tiles	All Windows to be In White Finished UVPC Roof to projecting Window Bay to front Elevation to be in Lead Efect GRP by Specialist	
75/T2.3	General wall Areas Red Brown Multi Brickwork, with Red Brick Plinth and Features with Blue Engineering Brickwork below DPC	Slate Grey Redland Stonewold II interlocking Concrete Roof Tiles	All Windows to be In White Finished UVPC Entrance Portico Detail to front Elevation to be in White GRP by Specialist	
76/T2.4	General wall Areas Buff Multi Brickwork, with Red Brick Quoins ,Features and Plinth - Blue Engineering Brickwork below DPC	Red/Brown Redland Stonewold II interlocking Concrete Roof Tiles	All Windows to be In White Finished UVPC Roof to projecting Window Bay to front Elevation to be in Lead Efect GRP by Specialist	Finishes to Shared Detached Garage as House No. 75 Garage Doors to be finished in White Paintwork
77/T2.3	General wall Areas Buff Multi Brickwork, with Red Brick Quoins ,Features and Plinth - Blue Engineering Brickwork below DPC	Red/Brown Redland Stonewold II interlocking Concrete Roof Tiles	All Windows to be In White Finished UVPC Roof to projecting Window Bay to front Elevation to be in Lead Efect GRP by Specialist	
78/T3	General wall Areas Red Brown Multi Brickwork, with Red Brick Plinth and Features with Blue Engineering Brickwork below DPC	Slate Grey Redland Stonewold II interlocking Concrete Roof Tiles	All Windows to be In White Finished UVPC Roof to projecting Window Bay to front Elevation to be in Lead Efect GRP by Specialist	
79/T3	General wall Areas Buff Multi Brickwork, with Red Brick Quoins ,Features and Plinth - Blue Engineering Brickwork below DPC	Red/Brown Redland Stonewold II interlocking Concrete Roof Tiles	All Windows to be In White Finished UVPC Roof to projecting Window Bay to front Elevation to be in Lead Efect GRP by Specialist	
80/ T2.3	General wall Areas Buff Multi Brickwork, with Red Brick Quoins ,Features and Plinth - Blue Engineering Brickwork below DPC	Red/Brown Redland Stonewold II interlocking Concrete Roof Tiles	All Windows to be In White Finished UVPC Roof to projecting Window Bay to front Elevation to be in Lead Efect GRP by Specialist	
81/T2.4	General wall in High Performance Render System Colour White with Blue Engineering Brickwork below DPC - Projecting Eaves Detail and Chimney Stack in Red Brown Multi Brickwork	Slate Grey Redland Stonewold II interlocking Concrete Roof Tiles	All Windows to be In White Finished UVPC Entrance Portico Detail to front Elevation to be in White GRP by Specialist	
82/T2.3	General wall Areas Buff Multi Brickwork, with Red Brick Quoins ,Features and Plinth - Blue Engineering Brickwork below DPC	Red/Brown Redland Stonewold II interlocking Concrete Roof Tiles	All Windows to be In White Finished UVPC Roof to projecting Window Bay to front Elevation to be in Lead Efect GRP by Specialist	
83/T3	General wall Areas Red Brown Multi Brickwork, with Red Brick Plinth and Features with Blue Engineering Brickwork below DPC	Slate Grey Redland Stonewold II interlocking Concrete Roof Tiles	All Windows to be In White Finished UVPC Roof to projecting Window Bay to front Elevation to be in Lead Efect GRP by Specialist	Finishes to Shared Detached Garage as House No. 75 Garage Doors to be finished in White Paintwork
84/T2.3	General wall Areas Red Brown Multi Brickwork, with Red Brick Plinth and Features with Blue Engineering Brickwork below DPC	Slate Grey Redland Stonewold II interlocking Concrete Roof Tiles	All Windows to be In White Finished UVPC Roof to projecting Window Bay to front Elevation to be in Lead Efect GRP by Specialist	
85/T2.4	General wall Areas Red Brown Multi Brickwork, with Red Brick Plinth and Features with Blue Engineering Brickwork below DPC	Slate Grey Redland Stonewold II interlocking Concrete Roof Tiles	All Windows to be In White Finished UVPC Roof to projecting Window Bay to front Elevation to be in Lead Efect GRP by Specialist	
86/T3	General wall Areas Buff Multi Brickwork, with Red Brick Quoins ,Features and Plinth - Blue Engineering Brickwork below DPC	Red/Brown Redland Stonewold II interlocking Concrete Roof Tiles	All Windows to be In White Finished UVPC Roof to projecting Window Bay to front Elevation to be in Lead Efect GRP by Specialist	Finishes to Detached Garage as House No. 86 Garage Doors to be finished in White Paintwork

House Type T3, T2.3 / T2.4 Group

SHDC
Planning & Development
0 4 FEB 2004
Ref 0971/03

A1 PLAN
Ref. A1

DETERMINED PLAN

REVISION:

Peter Humphrey Associates
ARCHITECTURAL DESIGN AND BUILDING

PROJECT
Residential Development
Off Sutton Bridge Road
Sutton Bridge, Lincolnshire

Building Finishes Schedule Sht. 4

CLIENT
Cannon Kirk Homes Ltd

DATE 08/2003 SCALE NTS JOB No. 2535 / P18 REV A

DO NOT SCALE FROM THIS DRAWING
COPYRIGHT: THIS DRAWING MUST NOT BE ISSUED, LOANED OR COPIED WITHOUT THE CONSENT OF PETER HUMPHREY ASSOCIATES

Peter Humphrey Associates
ARCHITECTURAL DESIGN AND BUILDING
TELEPHONE 01945 466 966
FAX 01945 466 433
E-MAIL:
info@peterhumphrey.co.uk
30 OLD MARKET WISBECH CAMBS PE13 1NB
British Institute of Architectural Technologists