KEY

	Existing Trees to be removed. See Ian Stemp Landscape Associates Tree report ref. IFS: 03.513.
	Trees to be retained Nos refer to Ian Stemp Landscape Associates Tree Report Ref. IFS.03.513
	Driveways and verge crossings to be Marshalls Keyblock Rectangular Block Paving 200 x 100 x 80 in Charcoal colour. Roadways to be Brindle colour.
	Tarmac surfacing
	1.8m high timber close boarded fencing
	2.2m high close boarded timber fencing
	1.8m high boundary wall
	Marshalls Block Paving to front paths, 200 x 100 x 65 in Terracotta. Laid in diagonal pattern as shown, with soldier course edge.
	Rear patios, pathways to rear patios to be constructed from 450 x 450 Chancery Flagstones by Marshalls.
o o	Bollards

All paths to front door and gate access to be 450 x 450 pcc slabs

DETERMINED PLAN

SHDC Planning & Development 26 NOV 2003

Revisions	Dwn.	Date
B: Garage & parking to plot 1 & associated car parking spaces 1-7 ammended.	ajc	25.11.03
A: Various minor amendments	cn	15.09.03

Project
PROPOSED DEVELOPMENT OFF BRIDGE ROAD, SUTTON BRIDGE, For CANNON KIRK.

Drawing
Proposed Hard Landscape
Sheet 1 of 4

Date: 14.08.03	Drawn: ifs/ajc
Dwg. No.: 03.513.002	Scale: 1:200 @ A1
Revision: B	Revision Date

IAN STEMP LANDSCAPE ASSOCIATES
LANDSCAPE ARCHITECTURE . LANDSCAPE PLANNING . URBAN LANDSCAPE DESIGN
STUDIO ONE, THE MEWS, 206 AVENUE ROAD EXTENSION, CLARENDON PARK, LEICESTER, LE2 3EL
Tel: 0116 270 1387 Fax: 0116 244 8840
email: ifs@stempla.fsnet.co.uk