

Planting Schedule						
Trees	Number	Abbreviation	Species	Specification	Girth	Height
18 No.	Ac	Acer campestre	Heavy Standard	Clear Stem min. 200 RB	12-14cm	3.5-4.0m
7 No.	ACEPLCS	Acer platanoides 'Crimson Sentry'	Advanced Nursery Stock	Clear Stem min. 200 RB	16-18cm	4.0-4.5m
2 No.	AcStr	Acer campestre 'Streetwise'	Advanced Nursery Stock	Clear Stem min. 200 RB	16-18cm	4.0-4.5m
7 No.	AgI	Ailnus glutinosa	Heavy Standard	Clear Stem min. 200 RB	12-14cm	3.5-4.0m
12 No.	BEPE	Betula pendula	Advanced Nursery Stock	Clear Stem min. 200 RB	12-14cm	3.5-4.0m
10 No.	BETPU	Betula pubescens	Advanced Nursery Stock	Clear Stem min. 200 RB	16-18cm	4.0-4.5m
2 No.	CARBET	Carpinus betulus	Advanced Nursery Stock	Clear Stem min. 200 RB	16-18cm	4.0-4.5m
2 No.	CARBETLU	Carpinus betulus 'Lucas'	Advanced Nursery Stock	Clear Stem min. 200 RB	16-18cm	4.0-4.5m
9 No.	Cav	Corylus avellana	Heavy Standard	Clear Stem min. 200 RB	12-14cm	3.5-4.0m
4 No.	Coal	Corylus colina	Advanced Nursery Stock	Clear Stem min. 200 RB	16-18cm	4.0-4.5m
6 No.	Cmo	Crataegus monogyna	Heavy Standard	Clear Stem min. 200 RB	12-14cm	3.5-4.0m
5 No.	FAGSY	Fagus sylvatica	Heavy Standard	Clear Stem min. 200 RB	12-14cm	3.5-4.0m
3 No.	GB	Ginkgo biloba	Advanced Nursery Stock	Clear Stem min. 200 RB	16-18cm	4.0-4.5m
2 No.	Ia	Ilex aquifolium	Heavy Standard	Clear Stem min. 200 RB	12-14cm	3.5-4.0m
2 No.	LIQST	Liquidambar styraciflua	Advanced Nursery Stock	Clear Stem min. 200 RB	16-18cm	4.0-4.5m
2 No.	MAGKO	Magnolia kobus	Advanced Nursery Stock	Clear Stem min. 200 RB	16-18cm	4.0-4.5m
3 No.	MAGLOME	Magnolia loebneri 'Merrill'	Advanced Nursery Stock	Clear Stem min. 200 RB	16-18cm	4.0-4.5m
3 No.	MAHP	Malus hugoensis	Advanced Nursery Stock	Clear Stem min. 200 RB	16-18cm	4.0-4.5m
2 No.	MALSY	Malus sylvestris	Heavy Standard	Clear Stem min. 200 RB	12-14cm	3.5-4.0m
4 No.	MALTS	Malus tschonoskii	Advanced Nursery Stock	Clear Stem min. 200 RB	16-18cm	4.0-4.5m
4 No.	Palp	Prunus avium Piena'	Advanced Nursery Stock	Clear Stem min. 200 RB	16-18cm	4.0-4.5m
12 No.	Pay	Prunus avium	Heavy Standard	Clear Stem min. 200 RB	12-14cm	3.5-4.0m
2 No.	Qr	Quercus robur	Heavy Standard	Clear Stem min. 200 RB	12-14cm	3.5-4.0m
1 No.	Sa	Salix alba	Heavy Standard	Clear Stem min. 200 RB	12-14cm	3.5-4.0m
4 No.	Sar	Sorbus aria	Heavy Standard	Clear Stem min. 200 RB	12-14cm	3.5-4.0m
12 No.	Sau	Sorbus aucuparia	Heavy Standard	Clear Stem min. 200 RB	12-14cm	3.5-4.0m
5 No.	Tc	Tilia cordata	Heavy Standard	Clear Stem min. 200 RB	12-14cm	3.5-4.0m
3 No.	TcGS	Tilia cordata 'Green Spire'	Advanced Nursery Stock	Clear Stem min. 200 RB	16-18cm	4.0-4.5m
14 No.	ULMNEW	Ulmus 'New Horizon'	Advanced Nursery Stock	Clear Stem min. 200 RB	16-18cm	4.0-4.5m
Shrubs						
Number	Abbreviation	Species	Specification	Height	Pot Size	Density
21 No.	AUCJAR	Aucuba japonica 'Rozannie'	Bushy	3/4 brks	30-40cm	5L 3/m²
134 No.	Cc	Cistus corbariensis	Bushy	3/4 brks	30-40cm	5L 4/m²
68 No.	Ccn	Comvolvulus cheorum	Bushy	3/4 brks	30-40cm	5L 3/m²
68 No.	CHDEF	Choisya 'Goldflingers'	Bushy	3/4 brks	30-40cm	5L 3/m²
67 No.	CISPUR	Cistus purpureus	Bushy	3/4 brks	30-40cm	5L 4/m²
75 No.	EfENG	Euonymus fortunei 'Emerald n' Gold'	Bushy	3/4 brks	30-40cm	5L 3/m²
60 No.	EISQ	Euonymus fortunei 'Silver Queen'	Bushy	3/4 brks	30-40cm	5L 3/m²
71 No.	FJOL ED	Fuchsia 'Lena Dalton'	Bushy	3/4 brks	30-40cm	5L 3/m²
7 No.	HEBMW	Hebe 'Mrs Winder'	Bushy	3/4 brks	30-40cm	5L 3/m²
24 No.	HEBNB	Hebe 'Nicola's Blush'	Bushy	3/4 brks	30-40cm	5L 3/m²
40 No.	HEBRA	Hebe rakaiensis	Bushy	3/4 brks	30-40cm	5L 3/m²
31 No.	Hi	Hypericum 'Hidcote'	Bushy	3/4 brks	30-40cm	5L 3/m²
94 No.	LAH	Lavandula angustifolia 'Hidcote'	Bushy	3/4 brks	20-30cm	3L 6/m²
84 No.	LaR	Lavandula angustifolia 'Rosea'	Bushy	3/4 brks	20-30cm	3L 6/m²
92 No.	LAVST	Lavandula stoechas	Bushy	3/4 brks	20-30cm	3L 6/m²
41 No.	MaA	Mahonia aquifolium 'Apollo'	Bushy	3/4 brks	30-40cm	5L 3/m²
77 No.	PACTEVA	Pachysandra terminalis 'Variegata'	Bushy	2/3 brks	20-30cm	3L 4/m²
38 No.	PARCA	Parahebe catarractae	Bushy	2/3 brks	20-30cm	3L 5/m²
127 No.	PERATBS	Paroskeia 'Blue Spire'	Bushy	3/4 brks	30-40cm	5L 5/m²
36 No.	POTFRABW	Potentilla fruticosa 'Abbotswood White'	Bushy	3/4 brks	30-40cm	5L 4/m²
7 No.	SiGP	Spiraea japonica 'Golden Princess'	Bushy	3/4 brks	30-40cm	5L 3/m²
27 No.	SiRu	Spiraea japonica 'Rubella'	Bushy	3/4 brks	30-40cm	5L 3/m²
164 No.	VHMAVA	Vinca major 'Variegata'	Bushy	2/3 brks	20-30cm	2L 6/m²

Native Hedge Mix 3						
Number	Abbreviation	Species	Specification	Height	Density	%
128 No.	Ac	Acer campestre	BR Double staggered row	60-80cm	5/m	10%
128 No.	Cav	Corylus avellana	BR Double staggered row	60-80cm	5/m	10%
625 No.	Cmo	Crataegus monogyna	BR Double staggered row	60-80cm	5/m	50%
66 No.	LIGVU	Ligustrum vulgare	BR Double staggered row	60-80cm	5/m	5%
128 No.	PRUSP	Prunus spinosa	BR Double staggered row	60-80cm	5/m	10%
128 No.	VIBLA	Viburnum lantana	BR Double staggered row	60-80cm	5/m	10%
68 No.	VIBOP	Viburnum opulus	BR Double staggered row	60-80cm	5/m	5%
Total :1269 No.						

Hornbeam Hedge						
Number	Abbreviation	Species	Specification	Height	Density	%
779 No.	CARBET	Carpinus betulus	BR Double staggered row	60-80cm	5/m	
Total :779 No.						

Skimmia Hedge						
Number	Abbreviation	Species	Specification	Height	Density	%
333 No.	Si	Skimmia japonica	Bushy	3/4 brks	C:30-40cm	5/m
Total :333 No.						

Escallonia Hedge						
Number	Abbreviation	Species	Specification	Height	Pot Size	Density
152 No.	EAB	Escallonia 'Apple Blossom'	Double staggered row	60-80cm	3L	4/m
Total :152 No.						

Privit Hedge						
Number	Abbreviation	Species	Specification	Height	Density	%
252 No.	LIGOVV	Ligustrum ovalifolium 'Variegatum'	Bushy	3/4 brks	C:40-60cm	4/m
Total :252 No.						

Box hedge						
Number	Abbreviation	Species	Specification	Height	Pot Size	Density
98 No.	Bse	Buxus sempervirens	20-30cm	2L	6/m	
Total :98 No.						

Native Shrub Mix						
Number	Abbreviation	Species	Specification	Height	Density	%
144 No.	CORSA	Cornus sanguinea	BR Branched	2/3 brks:1+1	60-80cm	1/m² 20%
144 No.	Cav	Corylus avellana	BR Branched	2/3 brks:1+1	60-80cm	1/m² 20%
144 No.	Cmo	Crataegus monogyna	BR Branched	2/3 brks:1+1	60-80cm	1/m² 20%
75 No.	ILEAQ	Ilex aquifolium	C-Leader With Lateralis	1+1	60-80cm	1/m² 10%
144 No.	PRUSP	Prunus spinosa	BR Branched	2/3 brks:1+1	60-80cm	1/m² 20%
75 No.	Rca	Rosa canina	BR Branched	2/3 brks:1+1	60-80cm	1/m² 10%
Total :726 No.						

Groundcover Mix 1						
Number	Abbreviation	Species	Specification	Height	Pot Size	Density
45 No.	CORSA	Cornus sanguinea	Bushy	2/3 brks	10-20cm	3L 4/m² 30%
37 No.	HEBALRE	Hebe albicans 'Red Edge'	Bushy	2/3 brks	10-20cm	3L 4/m² 20%
45 No.	HEUSN	Heuchera 'Snowstorm'	Full Pot		3L	4/m² 30%
24 No.	NEPRASN	Nepeeta racemosa 'Snowflake'	Full Pot		3L	4/m² 15%
Total :151 No.						

Medium Mix 1						
Number	Abbreviation	Species	Specification	Height	Pot Size	Density
16 No.	BRASU	Brachyglottis 'Sunshine'	Bushy	2/4 brks	30-40cm	5L 4/m² 15%
22 No.	ESCRCA	Escallonia 'Red Elf'	Bushy	2/4 brks	30-40cm	5L 4/m² 20%
22 No.	EISQ	Euonymus fortunei 'Silver Queen'	Bushy	2/4 brks	30-40cm	5L 4/m² 20%
22 No.	HEBNB	Hebe 'Nicola's Blush'	Bushy	2/4 brks	30-40cm	5L 4/m² 20%
27 No.	WEIMOB	Weigela 'Mont Blanc'	Bushy	2/4 brks	30-40cm	5L 4/m² 25%
Total :109 No.						

Medium Mix 2						
Number	Abbreviation	Species	Specification	Height	Pot Size	Density
42 No.	EfENG	Euonymus fortunei 'Emerald n' Gold'	Bushy	2/4 brks	20-30cm	3L 4/m² 20%
33 No.	HEBRA	Hebe rakaiensis	Bushy	2/4 brks	20-30cm	3L 4/m² 15%
42 No.	MaA	Mahonia aquifolium 'Apollo'	Bushy	3/4 brks	30-40cm	5L 4/m² 20%
42 No.	POTFRABW	Potentilla fruticosa 'Abbotswood White'	Bushy	3/4 brks	20-30cm	3L 4/m² 20%
52 No.	WEIRUM	Weigela 'Rumba'	Bushy	3/4 brks	30-40cm	5L 4/m² 25%
Total :211 No.						

Medium Mix 3						
Number	Abbreviation	Species	Specification	Height	Density	%
99 No.	EfENG	Euonymus fortunei 'Emerald n' Gold'	Bushy	3/4 brks	30-40cm	4/m² 25%
63 No.	HAG	Hebe 'Autumn Glory'	Bushy	3/4 brks	30-40cm	4/m² 15%
61 No.	HEBRA	Hebe rakaiensis	Bushy	3/4 brks	30-40cm	4/m² 20%
99 No.	LAVANAL	Lavandula angustifolia 'Alba'	Bushy	3/4 brks	30-40cm	4/m² 25%
63 No.	WEISN	Weigela 'Snowflake'	Bushy	3/4 brks	30-40cm	4/m² 15%
Total :405 No.						

Large Mix 1						
Number	Abbreviation	Species	Specification	Height	Pot Size	Density
38 No.	CEABLC	Ceanothus 'Blue Cushion'	Bushy	3/5 brks	30-40cm	5L 3/m² 18%
43 No.	CORSTKEG	Cornus stolonifera 'Kelsey Gold'	Bushy	3/5 brks	30-40cm	5L 3/m² 20%
38 No.	EeGE	Elaeagnus ebbingei 'Gilt Edge'	Bushy	3/5 brks	30-40cm	5L 3/m² 18%
23 No.	ILEAQSQ	Ilex aquifolium 'Silver Queen'	Bushy	3/5 brks	30-40cm	5L 3/m² 10%
33 No.	VIBPRIA	Viburnum tinus 'Eve Price'	Bushy	3/5 brks	30-40cm	5L 3/m² 15%
42 No.	WEIFLPOP	Weigela florida 'Follis Purpurea'	Bushy	3/5 brks	30-40cm	5L 3/m² 19%
Total :217 No.						

Large Mix 3						
Number	Abbreviation	Species	Specification	Height	Density	%
42 No.	CHOTE	Choisya ternata	Bushy	3/4 brks	30-40cm	3/m² 20%
42 No.	CORSAMF	Cornus sanguinea 'Midwinter Fire'	Bushy	3/4 brks	30-40cm	3/m² 20%
42 No.	CORSTKEG	Cornus stolonifera 'Kelsey Gold'	Bushy	3/4 brks	30-40cm	3/m² 20%
42 No.	PRR	Photinia fraseri 'Red Robin'	Bushy	3/4 brks	30-40cm	3/m² 20%
42 No.	WEIFLVA	Weigela florida 'Variegata'	Bushy	3/4 brks	30-40cm	3/m² 20%
Total :210 No.						

Low Shrub Mix						
Number	Abbreviation	Species	Specification	Density	Weight	
32 No.	CEAREPA	Ceanothus thyrsiflorus repens	Bushy	3/4 brks	4/m²	
32 No.	HEBRA	Hebe rakaiensis	Bushy	3/4 brks	4/m²	
32 No.	LONNMG	Lonicera nitida 'May Green'	Bushy	3/4 brks	4/m²	
32 No.	PIOL	Prunus laurocerasus 'Otto Luyken'	Bushy	3/4 brks	4/m²	
32 No.	SPJIAF	Spiraea japonica 'Fire Light'	Bushy	3/4 brks	4/m²	
Total :160 No.						

Ornamental Mix 1						
Number	Abbreviation	Species	Specification	Density	Weight	
65 No.	EISQ	Euonymus fortunei 'Silver Queen'	Full Pot	3/4 brks	3/m²	
76 No.	HELAR	Helleborus argutifolius	Full Pot		3/m²	
65 No.	LAVANVE	Lavandula angustifolia 'Vera'	Bushy	3/4 brks	3/m²	
52 No.	PENOR	Pennisetum orientale	Full Pot		3/m²	
Total :258 No.						

Osmanthus burkwoodii Hedge 1						
Number	Abbreviation	Species	Specification	Density	Weight	
353 No.	Ob	Osmanthus burkwoodii	Bushy	3/5 brks: Double Staggered	4/m	
Total :353 No.						

Amenity Grass Mix						
Emorsgate EL1 Flowering Lawn Mixture. Sown at 40kg/ha						

Wetgrass Mix						
Emorsgate EM8 Meadow Mixture for wetlands. Sown at 40kg/ha						

Wildflower Grass Mix						
Emorsgate EM2 Standard General Purpose Meadow Mixture. Sown at 40kg/ha						



NOTES:
Based upon the Ordnance Survey map with permission of The Controller of Her Majesty's Stationery Office, © Crown Copyright.
Aspect Landscape Planning Ltd, West Court, Hardwick Business Park, Noral Way, Banbury OX16 2AF.
License: 100045345

Copyright reserved