Rev. No.	REVISION	Date	Drawn By	Checked By
A	Soakaway information added	25.9.03	AJMB/BC	AJMB
B	Plots 9-13 revised			

Written dimensions to be taken. Do not scale off the drawing.
Any discrepancies, written or scaled, should be brought to the attention of the engineer immediately.
This drawing to be read in conjunction with the relevant Bills of Quantities and Local Authority Specification.
CDM NOTE: The design has been undertaken as far as possible to avoid risks to health and safety or to reduce and control the effects of any unavoidable risks.
All relevant information identifying the unavoidable risks has been passed to the planning supervisor for inclusion in the Health & Safety plan.
The Health & Safety plan will be issued by the planning supervisor with these drawings.

WORMALD, BURROWS PARTNERSHIP

Civil Engineering Consultants
12a & 14a Hitchin Street, Tel 01767 317244
Biggleswade, Beds SG18 8AX, U.K. Fax 315434

Project

Proposed Development at:-
Bridge Road, Sutton Bridge

Drawing Description

Private Drainage - Sheet 3 of 3

Client

Allison Homes Eastern Ltd
Banbury Close
West Elloe Avenue
Spalding
Lincolnshire PE11 2BS

Architect

Drawing Number: E1332/7/B

Drawn By: AJMB/BC
Date 2.9.03

Scale: 1: 200

Checked By: AJMB
Date 25.9.03

EAQA REGISTERED COMPANY ISO 9001:1994 CERT NO.00

Ref. APPLICATION

Ref. 13/22/03


27 FEB 2004

DEVELOPMENT PLAN

Planning Dept

Received

SOAKAWAY
2 Units High - Width & Length Varies See Plan



DESIGN OF SOAKAWAYS

From BRE Digest 365: Rainfall Ratio
r=0.40 for this location.
Soakage rate=2.5x10^{-6}m/sec based on tests made by Abatech International Ltd on 25.6.2003.

NOTES
1. Soakage through the base has been added to that through the walls as clogging is considered unlikely due to the geotextile protection.
2. Edge of soakaway should not be nearer than about 5m from any building.
3. Soakage rates shall be verified on site by geotechnical consultant & notified to the Engineer.
4. All soakaways shall be located in clean uncontaminated ground.
5. The construction method is by using prefabricated cell units with 95% voids, (Wavin Aquacell or similar approved) The unit size is 1.0m long x 0.5m wide x 0.4m high. All soakaways have been designed to be 2 units high (ie 0.8m) with plan dimensions as marked on plan.
6. The Aquacell drainage units shall be installed strictly in accordance with the manufacturers instructions.
7. Permeable geotextile material shall be placed around the base, sides,ends & top of the Aquacell units. O$_{90}$ pore size of 0.2mm or less to prevent ingress of fines.

DRAINAGE NOTES

All works to comply with Building Regulations.2000 Approved Document H,2002 Edition
Private drain connections to adoptable sewers to be clayware pipes.
Remaining private drains to be 110mm dia. U.P.V.C. or 100mm clayware unless stated.
Private sewers serving more then 10 dwellings to be 150mm dia
All pipe chambers and fittings to be installed, bedded and backfilled in accordance with the manufacturers instructions.
Private drains and sewers which pass adjacent to building foundations to be constructed in accordance with Part H.1. of the Building Regulations.
All private drains to incorporate preformed inspection and shallow access chambers where possible.
Traditional chambers (private) to be constructed using precast concrete sections with 150mm concrete surround.

Depth to I.L.	Min. chamber size (internal).
0.6m or less	225mm x 100mm or 190mm dia
0.9m or less	450mm x 450mm (normally a preformed chamber,450mm dia)
1.2m or less	450 x 450mm (normally a preformed chamber,450mm dia)
1.5m or less	1200mm x 675mm or 1200mm dia. (pipe up to 225mm dia only)
Over1.5m	1200mm x 1000mm or 1200mm dia. (pipe up to 225mm dia only)

Rainwater downpipes to be connected directly to surface water drain via 68/110mm adaptors, removable to allow for rodding.
Position of yard gullies shown in garage drives are nominal only and may be adjusted on site.
All drains in the vicinity of proposed trees to be constructed in accordance with the requirements of current N.H.B.C. standards.
All back inlet gullies to be roddable.

ADOPTABLE DRAINAGE LEGEND

Existing foul water sewer
Existing surface water sewer
Proposed foul water sewer (to be adopted)
Proposed surface water sewer (to be adopted)
Proposed backdrop (on adopted sewer)
Proposed trapped road gully (150mm outlet) G

PRIVATE DRAINAGE LEGEND

Proposed foul water drain
Proposed surface water drain
Proposed inspection chamber (traditional) or
Proposed preformed inspection chamber (depth 0.9m/1.2m or less) or
Proposed preformed inspection chamber (depth 600mm or less) or
Proposed shallow access chamber (normally preformed 225mm or 250mm dia)
Proposed rodding eye RE
Proposed chamber invert level 7.50
Proposed trapped gully in drives
Suspended slab, where appropriate SS
Proposed slab level SL 9.750
Proposed soakaway
Target levels to car parks x 7.820

rwp... ○ svp... ● svp via... ◉ w/c... ○ sink... ○ big... ■ vent pipe... ○ vent required at head of system

NOTE
Where durgo valves are used they should not adversely effect the amount of ventilation necessary for the below ground system which is normally provided by the open stacks of the sanitary pipework.