PROPOSED WAREHOUSE EXTENSION

EXISTING TREE SCREEN

P.E.T.S. LANE

PROPOSED TREE AND UNDERSTOREY PLANTING

35

34

32

31

33

20

21

S.W.D.

LOADING AREA

CAR PARKING

OFFICES

I.B.C. STORAGE

ENCLOSED INTAKE HOPPER & ELEVATOR

INTAKE CONVEYOR

ELECTRICITY SUB STATION

PROPOSED AREA OF OPEN STORAGE AND GENERAL INDUSTRY ON DEVELOPMENT LAND

EXTENSION OF PERIMETER PLANTING

PROPOSED 4m HIGH EARTH BUND

EXISTING MATURE TREES AND HEDGE

NEW ACCESS ROAD

TRANSPARENT SECTION OF ACOUSTIC FENCING

EXISTING QUAY

2·0m ACOUSTIC FENCING

PROPOSED OPEN STORAGE AREA

MEAN HIGH WATER

RIVER NENE

NENE OUTFALL CUT

MEAN HIGH WATER

N

## PROPOSED PLANTING

°P °P °P °P °P °P

T× T× T× H× T× H× T× T× T× T×

×H ×T ×T ×T ×T ×T ×T ×H ×T ×T ×T

SCALE 1:100.

TREES

POPULUS TREMULA 'ASPEN' 180–240cm feathered. planted at 3m centres

UNDERSTOREY PLANTING

ILEX AQUIFOLIUM 25–30cm 1 litre pot (HOLLY 20%)
CRATAEGUS MONOGYNA 30–45cm (1+1) bushy (THORN 80%)

Trees to be staked and tied and subjects to be protected by appropriately sized tree tubes

UNDETERMINED PLAN

SHDC PLANNING & DEVELOPMENT 17 NOV 2003 Ref. 1373/03

REV 'A' NOV 03 INCLUSION OF OPEN STORAGE ON DEVELOPMENT LAND AND CREATION OF BUND AND EXTENSION OF PERIMETER PLANTING

# PORT SUTTON BRIDGE LTD

PROPOSED OPEN STORAGE, EARTH BUND, ACCESS ROAD AND ACOUSTIC FENCE

DWG NO; 473/6/102

SCALE 1:2500

NOVEMBER 2003

Chartered Town Planners
Chartered Landscape Architects
Robert Doughty Consultancy Limited
32 High Street, Helpringham, Sleaford, NG34 0RA Tel: (01529) 421646 Fax: (01529) 421358