

POD
Designs

Tel: 01529 240 407

PROJECT:
Proposed Conversion of Barns at
Fen Farm Barns, Grange Hill Road,
Tydd St. Mary's Fen, Wisbech,
CAMB.

DRAWING:
Details of Doors D2 & D3.

DRAWN: rpm	DATE: Dec 06	SCALE: 1:20 & 1:2
----------------------	------------------------	-----------------------------

DWG No
3257 - 19

SHDC
PLANNING & DEVELOPMENT
- 9 JAN 2007
Ref: 004/07

DETE
P

Replace timber lintel
*arch until size to
match extg. exactly

Replace 2nd extg.
thresholds size to
match extg. exactly

ELEVATION & PLAN OF D2 (2N°)

VERTICAL SECTION D2 (2N°)

HORIZONTAL SECTION D2 (2N°)

ELEVATION & PLAN OF D3

VERTICAL SECTION (D3)

HORIZONTAL SECTION (D3)

NOTES

- Details shown are to give indication only of looks of joinery for planning purposes. Construction of joinery details to be agreed with client.
- All glazed doors to be: hardwood (linco) ie with double glazed units 16mm cavity with solar reflective glass (E-glass) to give min U-value of 2.0 w/m². (See client if upgrade of glazing to argon filled cavity & laminated glass is req'd.)
- All joinery to be preservative treated at works. Natural clear finish eg linseed oil (type & method to be agreed with client & sample to be provided to Planning Authority)
- All glazed door units to be hung on steel bushed butt hinges.
- All window & door frames to be set back 25mm from ext. face of bulk to match extg. All cills, head & reveals to be lined with Celotex TB3012 (12mm thick) insulation with 12.5mm thick plasterboard fixed in accordance with manufacturers details.
- All glazing 800mm above finished F.L. in wall & 1500mm in doors to be safety glass as BS.6206 & Approved Doc N.

**DETERMINED
PLAN**