









FRONT ELEVATION


SIDE ELEVATION




GARAGE PLAN



REAR ELEVATION




SIDE ELEVATION




GARAGE ELEVATIONS

SOIL DRAINS.
All drains to 600 Gallon Septic tank.
All drains in 110mm dia pvc with flexible joints and laid to 1-40 falls in 150 mm pea gravel bed and surrounds.Cap trenches beneath driveway with 1:3:6 concrete.Sleeve all pipes through or under raft with 150mm dia pvc pipes.
Inspection chambers of D.S.M.A type unversal to suit manufacturers instructions and installation details,for depth and dia.
The sub-irrigational drainage system to the cesspool is to be determined by Percolation tests in accordance with provisions of clause 15.3.2 of BS6927:1983. The applicant is responsible for carrying out the tests and the minimum requirement is 25m of sub-irrigational drainage or such length as may be determined by the tests, whichever is the greater. It is recommended by the Council that the septic tank/cesspool and settlement tanks are sited a minimum 12m from dwelling. It is essential that the drainage falls to the septic tank are 1 in 40 and that the tank, particularly the bottle type is modified by reducing its neck length by cutting to ensure that both inlet and outlet are maintained above ground water level. Applicants are reminded that the consent of NRA must be sought under the provisions of Section 34 of the Control of Pollution Act 1974, for permission to discharge sewage effluent into the underground strata. Anglion Water DO NOT permit septic tank soakaway systems to be situated within 5m of any watercourse or to discharge effluent directly or indirectly into the aquifer.
Should the percolation test prove unsatisfactory for septic tank drainage due to impervious soil conditions such as clay, then a cesspool of 18,000 litres (4000 Gallons) capacity must be used.
SOIL WASTES.
Bath in 50mm dia pvc,Basins and sinks in 40mm dia pvc all with 75mm deep seal P traps.All wastes routed seperately to connect to svp. Svp's in 110mm dia pvc and terminating min 1000mm above opening windows.
STORM DRAINS.
All drains as specified for soil drains to 1m cube rubble filled soakaways min 5m from buildings.
Gutters 65mm square line UPVC. Down pipes in 65mm dia pvc.

MECHANICAL VENTILATION.
Bathroom/Ensuite and WCs to have mechanical extractors giving min 15 litres sec extraction,ducted to open air.Kitchen/Utility to have extraction at a rate of 60litres sec(or ducted cooker hood at 30litres sec)
All habitable rooms to have background ventilation of 8,000mm sq and toilets/bathrooms 4,000mm sq.
HEATING AND HOT WATER.
Oil fired non condensing domestic central heating boiler with balanced flue and cage guard.High efficiency panel radiators to all rooms all with thermostatically controlled valves
Domestic hot water and Central heating systems to be seperately zoned by motorised valves...
CEILINGS.
Ceilings of 12.5mm Plasterboard and skim or Artex finish through out to BS. 1230 part 1 with sealed and supported cross joints and timber noggins to edges of boards size 30x47mm.
AIRING CUPBOARD.
Install 117 litre hot water cylinder of the pre insulated type and vented/system. Install 3kw immersion heater and thermo stat .Provide three tiers of slatted shelves within cupboard
SMOKE DETECTION.
Hard wired smoke detection sensors to be located in positions labelled DS. Units to be hardwired in position within 3m of bearoom doors and 7m of habitable room doors.All to B.S 5446 Pt 1 1990 with battery back up and inter connected to seperate fuse board. ALL UNITS CEILING MOUNTED.
ELECTRICS.
Electrical installation to comply with 15th Edition IEE wiring regulations.Note provide lighting in roof space for safe access and working to roof tanks(close to hatch).
CONDITIONAL APPROVALS.
NOTE:
Non standard roof trusses.
The main contractor will be responsible for obtaining and submitting for approval, Calculations from the truss manufacturer to the building inspector.





Vertical tile hanging to dormer face and cheeks fixed to manufacturers instructions over felt and battens and 15mm exterior grade ply insulate between vertical studs 100x38mm at 400 c-c with 100mm fibre glass Inner lining of12.5mm plasterboard and skim over 1200g polythene.

DAVID BROKER DESIGN SERVICES

2000 CONCEPT ARCHITECTURE COMPUTER AIDED DESIGN

CLIENT

MR J. WHITWELL, LUTTONGATE RD.

SUTTON ST. EDMUND

NOTES:-
FOUNDATIONS.
Concrete strip foundations, min depth 1000mm
750mm wide to cavity walls, 600mm to internal walls.
Founds to be 250mm thick.
FLOOR
150mm consolidated and blinded hardcore backfilled and rammed to internal founds. 50mm Jablite, 1200g polythene DPM turned up at sides and linked to DPC. 100mm oversite concrete with A142 mesh in top for crack control 50mm cement sand screed finish.
D.P.M
Provide 1200g Polythene DPM over floor insulation turned up at sides and linked to DPC.
D.P.C.
Install Astos/High Load or similar dpc min 150mm above finished ground level and to sides of all openings in cavity walls.Tray d.p.c over all IG Lintels with weepholes to outer leaf.
Dpc,s to reveals to be insulated type, Damcore or similar.
Dpc to chimney above roof intersection to be of 2 courses of class B Engineering bricks.
WALL.
Outer leaf of Facing bricks,65mm cavity with 65mm Superglass insulation.6no stainless steel wire ties per 1m sq and cavity closed at roof and reveals with blockwork.
Inner leaf of 100mm aerioated blocks maximum density 1100kg/m
Movement joints as indicated. Incorporate brickfor or similar expanded metal to mortar coarsing 215mm below all windows
Inner face of all blockwork rendered and skimmed.
Cavity to extend min 150mm below dpc at perimeters.
FIRST FLOOR
Floor joists integral to trusses as manufacturers drawings
SC3 Grade timber throughout unless otherwise specified.
All joist to be at max 450mm c-c.
Joists parallel to walls, strapped to walls at max 2m c-c with 30x5x1200mm straps and fixed to softwood noggins between joists.
Spans over 2m to have Herringbone bracings at mid span in 38x 38mm timber or Catnic h/b.Spans over 4.5m same but at 1third c-c.Double joists beneath all studwork partitions and fix together with 12mm dia coach bolts and washers at 1.5m c-c, and 150mm from ends.Incorporate joist size block bondings between joists where partitions are perpendicular to joist span.Treble joists to Stair trimmers,infills and ends fixed with M/S hangers.
Floor of 18mm Moisture resistant chipboard t&g with P.V.A glued joints and ducted for access to all pipework.Provide support noggins beneath all joints.
STUDWORK.
100x38mm studs at 400mm max c-c OF 100x75mm sole plates and incorporating 2 rows of horizontal noggins at 1/3 height
Doors and frames as indicated and clad both sides with 12.5 mm Plasterboard and skim.Fill void with Superglass insulation.
GLAZING.
All windows Hardwood or UPVC double glazed with 20mm sealed units. All opening windows and doors to have full draft seals.
Opening lights to give 1/20th floor area in ventilation
All glass to be Hardened or toughened to B.S 6262 with safety glass to B.S 6206 CLASS B.
ROOF
Concrete interlocking tiles laid to manufacturers instructions on sarking felt and tile battens 25x38mm. on Trussed Rafters designed and fabricated to BS.5268 at 450mm c-c at 42 deg Pitch and braced together to BS.5268 1985 pt3. 100x25mm binders at joist and ridge nodes and at plane of truss webs.Install dormishing trusses/layboards and valley trays or tiles to roof intersections and manufacturers compound truss as appropriate
Diagonal bracing 100x25mm running from eaves to inner binders on top of ceiling joists and inner truss plane.75x100mm wall plates
Facia board offset 450mm from brickwork.6mm masterboard soffit with continuous Gildevale soffit vent strip.Code 4 stepped lead flashing at roof wall abutments and internal cavity stepped dpc tray.Trusses fixed to 75x100mm sw wall plate with galvanised ms truss clips.Plate strapped to blockwork with Catnic straps 1200x5mm at 2m c-c.Rafters strapped to gables with 1200x5mm straps spanning min 3no rafters and fixed to 75x38 mm noggins between rafters.Ceiling joists strapped likewise.
Tank supports 2No 47x200mm SC3 bearers on 2 No 47x200mm trimmers,supported on min 4 No trussed rafters and placed at node points of trusses.
All pipework outside insulated areas to be fully lagged
Area beneath roof tank to be uninsulated to prevent freezing.
INSULATION
100mm fibre glass between roof joists,100mm fibre glass across joists. Cavity wall insulation 65mm Superglass.
STAIRS.
Boulton and Poul standard manufactured staircase as indicated manufactured to BS 585.
Going220mm Rise 210mm Tread depth 250mm.Pitch max 42 deg.clear width 1000mm Handrail with intermediate newel posts ,height 900mm(min 840mm) above pitch line and to landings terminating in scrolls or other suitable fittings.
Ensure min 2m headroom above all treads.No opening between ballustrades or between treads to allow the passage of a 100mm dia sphere.Ballustrading to be constructed vertically to avoid childrens temptation to climb.Provide artificial lighting over stairs with two way switch from ground and first floor.Contractor to check stair dimensions on site before ordering or fabrication.

DRAWING/FILE No 221JW1
DRAWING No 1 OF 1
SCALE 1:50
DATE 18/3/98
DRAWN GL

PROPOSED CHALET PLANS AND ELEVATIONS

SOUTH HOLLAND DC HOUSING & PLANNING 26 MAR 1998 Ref: 0334/98

Issued	
Revisions	

ARCHITECTURAL TECHNICIANS
DANBROOKE HOUSE STATION ROAD
WISBECH ST MARY
WISBECH CAMBS.PE13 4RW
Telephone 01945410421 Facsimile 01945410400