







TYPICAL EAVES DETAIL 1:20



TYPICAL ROOF DETAIL 1:20



STRIP FOUNDATIONS SHOWN FOR DIAGRAMATICAL PURPOSES ONLY

TYPICAL SECTION

GLAZING.
All windows hardwood or uPVC units double glazed with 20mm sealed units. All opening windows and doors to have full draft seals including the loft hatch, (loft hatch to be fitted with suitable fastening to compress seal)
Opening lights to give 1/20th floor area in ventilation
All glass to be Hardened or toughened to B.S 6262 with safety glass to B.S 6206 CLASS B.

AIRING CUPBOARD.
Install 117 litre hot water cylinder of the pre insulated type, insulation to cylinder to be 50mm.
and vented/system. Install 3kw immersion heater and thermo stat .Provide three tiers of slatted shelves within cupboard

STAIRS.
Boulton and Paul standard manufactured staircase as indicated manufactured to BS 585.
Going 220mm Rise 210mm Tread depth 250mm.Pitch max 42 deg clear width 1000mm Handrail with intermediate newel posts .height 900mm(min 840mm) above pitch line and to landings.terminating in scrolls or other suitable fittings.
Ensure min 2m headroom above all treads.No opening between balustrades or between treads to allow the passage of a 100mm dia sphere.Ballustrading to be constructed vertically to avoid childrens temptation to climb.Provide artificial lighting over stairs with two way switch from ground and first floor.Contractor to check stair dimensions on site before ordering or fabrication.

MECHANICAL VENTILATION.
Bathroom/Ensuite and WCs to have mechanical extractors giving min 15 litres sec extraction,ducted to open air.Kitchen/Utility to have extraction at a rate of 60litres sec(or ducted cooker hood at 30litres sec)
All habitable rooms to have background ventilation of 8,000mm sq and kitchen/utility,toilets/bathrooms 4,000mm sq.
(Provided by trickle vents in window heads).


SMOKE DETECTION.
Hard wired smoke detection sensors to be located in positions labelled DS. Units to be hardwired in position within 3m of bedroom doors and 7m of habitable room doors.All to B.S 5446 Pt 1,1990 with battery back up and inter connected to seperate fuse board. ALL UNITS CEILING MOUNTED.

ELECTRICS.
Electrical installation to comply with 15th Edition IEE wiring regulations.Note provide lighting in roof space for safe access and working to roof tanks(close to hatch).


CHIMNEY.
Chimney to be lined full height with 225mm dia clay rebated liners laid socket upward.Maximum offset from the vertical 30deg and terminating min 1000mm above roof junction.Fire place jambs 200 mm thick.Fire place to be capable of burning smokeless fuel and to have flue throat restrictor,Flue cross sectional area to be min 20% of fire grate plan area.Provide 2 no 215mm sq air bricks to lounge for ventilation to open fire.

CEILINGS.
Ceilings of 12.5mm Plasterboard and skim or Artex finish through out to BS. 1230 part 1 with sealed and supported cross joints and timber noggins to edges of boards size 30x47mm.


SOIL DRAINS.
All drains to 600 Gallon Septic tank.
All drains in 110mm dia pvc with flexible joints and laid to 1-40 falls in 150 mm pea gravel bed and surrounds.Cap trenches beneath driveway with 1:3:6 concrete.Sleeve all pipes through or under raft with 150mm dia pvc pipes.
Inspection chambers of O.S.M.A type unversal to suit manuf acturers instructions and installation details,for depth and dia.
The sub-irrigational drainage system to the cesspool is to be determined by Percolation tests in accordance with provisions of clause 15.3.2 of BS6927:1983. The applicant is responsible for carrying out the tests and the minimum requirement is 25m of sub-irrigational drainage or such length as may be determined by the tests, whichever is the greater. It is recommended by the Council that the septic tank/cesspool and settlement tanks are sited a minimum 12m from dwelling. It is essential that the drainage falls to the septic tank are 1 in 40 and that the tank, particularly the bottle type is modified by reducing its neck length by cutting to ensure that both inlet and outlet are maintained above ground water level. Applicants are reminded that the consent of NRA must be sought under the provisions of Section 34 of the Control of Pollution Act 1974, for permission to discharge sewage effluent into the underground strata. Anglian Water DO NOT permit septic tank soakaway systems to be situated within 5m of any watercourse or to discharge effluent directly or indirectly into the aquifer.
Should the percolation test prove unsatisfactory for septic tank drainage due to impervious soil conditions such as clay, then a cesspool of 18,000 litres (4000 Gallons) capacity must be used.



REVEAL INSULATION POSITIONS



GARAGE PLAN



TYPICAL SECTION

SOIL WASTES.
Both in 50mm dia pvc,Basins and sinks in 40mm dia pvc all with 75mm deep seal P traps.All wastes routed seperately to connect to svp. Svp's in 110mm dia pvc and terminating min 1000mm above opening windows.

STORM DRAINS.
All drains as specified for soil drains to 1m cube rubble filled soakaways min 5m from buildings.
Gutters 65mm square line UPVC. Down pipes in 65mm dia pvc.

HEATING AND HOT WATER.
Oil fired non condensing domestic central heating boiler with conventional flue through roof with cowl.
.High efficiency panel radiators to all rooms, all with thermostatically controlled valves. Domestic hot water and Central heating systems to be separately zoned by motorised valves.
The space heating system should be fitted with a boiler interlock to prevent unnecessary boiler cycling.

CONDITIONAL APPROVALS.
Required for:
Non standard roof trusses.
The main contractor will be responsible for obtaining and submitting for approval, Calculations from the truss manufacturer to the building inspector, before trusses are installed.

SOUTH HOLLAND DC
HOUSING & PLANNING
15 JUL 1998
Ref: 0385/98

DETERMINED

DAVID BROKER DESIGN SERVICES
2000
CONCEPT
ARCHITECTURE
COMPUTER AIDED DESIGN

CLIENT MR & MRS BISHOP
PROPOSED DWELLING HOUSE AND GARAGE

NOTES:-
FOUNDATIONS.
Concrete reinforced foundations strictly in accordance with Structural Engineers details to take into account site conditions and soil report.

FLOOR.
Concrete reinforced floor as specified by Structural Engineer.
Floor finish to consist of 50mm Jablite insulation over raft slab. 1200g DPM turned up at sides and linked with DPC. Finished with a 75mm sand and cement screed.

D.P.M
Provide 1200g Polythene DPM over floor insulation turned up at sides and linked to DPC.

D.P.C
Install Astos/High Load or similar dpc min 150mm above finished ground level and to sides of all openings in cavity walls.Tray d.p.c over all IG Lintels with weepholes to outer leaf.
Dpc,s to reveals to be insulated type, Damcare or similar.
Dpc to chimney above roof intersection to be of 2 courses of class B Engineering bricks..

WALL.
Outer leaf of Facing bricks,65mm cavity with 65mm Superglass insulation. 5no stainless steel wire ties per 1m sq and cavity closed at roof and reveals with blockwork.
inner leaf of 100mm aerated blocks maximum density 1100kg/m
Movement joints as indicated. Incorporate bricktor or similar expanded metal to mortar coarsing 215mm below all windows
Inner face of all blockwork rendered and skimmed. Internal faces of steel lintels to be covered with min. 15mm lightweight plaster.
Cavity to extend min 150mm below dpc at perimeters.

FIRST FLOOR.
Floor joists as indicated on drawing all timber SC3 graded.All joists at max 400mm c-c with ends having min 100mm bearing.
Joists parallel to walls, strapped to walls at max 2m c-c with 30x5x1200mm straps and fixed to softwood noggins between joists.
Spans over 2m to have Herringbone bracings at mid span in 38x 38mm timber or Catnic h/b.Spans over 4.5m same but at 1third c-c Double joists beneath all studwork partitions and fix together with 12mm dia coach bolts and washers at 1.5m c-c, and 150mm from ends.Incorporate joist size block bondings between joists where partitions are perpendicular to joist span.Treble joists to Stair trimmers,Infills and ends fixed with M/S hangers.
Floor of 18mm Moisture resistant chipboard t&g with P.V.A glued joints and ducted for access to all pipework.Provide support noggins beneath all joints.

STUDWORK.
100x38mm studs at 400mm max c-c Of 100x75mm sole plates and incorporating 2 rows of horizontal noggins at 1/3 height
Doors and frames as indicated and clad both sides with 12.5 mm Plasterboard and skim.Fill void with Superglass insulation.

ROOF.
Redland double Roman roof tiles laid to manufacturers instructions on sarking felt and tile battens 25x38mm. on Trussed Rafters designed and fabricated to BS.5268 at 600mm c-c at 40 deg Pitch and braced together to BS.5268 1985 pt3. 100x25mm binders at joist and ridge nodes and at plane of truss webs.Install deminishing trusses/layboards and valley trays or tiles to roof intersections and manufacturers compound truss as appropriate.
Diagonal bracing 100x25mm running from eaves to inner binders on top of ceiling joists and inner truss plane.75x100mm wall plates

Continuous Glidevale eaves ventilation strip. Equivalent to 25mm wide opening full length of all eaves. Code 4 stepped lead flashing at roof wall abutments and internal cavity stepped dpc tray.Trusses fixed to 75x100mm sw wall plate with galvanised ms truss clips.Plate strapped to blockwork with Catnic straps 1200x5mm at 2m c-c.Rafters strapped to gables with 1200x5mm straps spanning min 3no rafters and fixed to 75x38 mm noggins between rafters.Ceiling joists strapped likewise.
Tank supports 2No 47x200mm SC3 bearers on 2 No 47x200mm trimmers,supported on min 4 No trussed rafters and placed at node points of trusses.
Flashings code 4 Lead at all roof wall/chimney abutments.
Area beneath roof tank to be uninsulated to prevent freezing.

INSULATION.
100mm fibre glass between roof joists,100mm fibre glass across joists. Cavity wall insulation 65mm Superglass.
Loft hatch to be insulated.
All pipework outside insulated areas to be fully lagged with 12mm Neoprene foam.

LOCATION PLAN 1-2500
REPRODUCED FROM THE ORDNANCE SURVEY MAP BY DAVID BROKER DESIGN SERVICES WITH THE SANCTION OF THE DIRECTOR GENERAL, ORDNANCE SURVEY,FOR BUSINESS USE. LICENCE No AR 375659.

HEALTH AND SAFETY C.D.M REGULATIONS 1995
THE CLIENT/DEVELOPER AND BUILDING CONTRACTOR/SUB CONTRACTOR ARE ADVISED TO AQUAINT THEMSELVES WITH THE IMPLICATIONS AND REQUIREMENTS OF THIS BUILDING PROJECT

DRAWING/FILE No 395 TB3
DRAWING No 1 OF 2
SCALE 1:50 1:100
DATE 19/11/97
DRAWN GL
FLOOR PLANS and SECTIONS


Issued	
Revisions	

ARCHITECTURAL TECHNICIANS
DANBROOKE HOUSE STATION ROAD
WISBECH ST MARY
WISBECH CAMBS.PE13 4RW


395TB3 Plotted: Tue Jul 14 11:10:28 1998

DAVID BROKER DESIGN SERVICES
2000
CONCEPT
ARCHITECTURE
COMPUTER AIDED DESIGN


CLIENT MR & MRS BISHOP
PROPOSED SUN LOUNGE WITH BEDROOM OVER




PROPOSED SIDE ELEVATION PROPOSED REAR ELEVATION PROPOSED SIDE ELEVATION



PROPOSED FRONT ELEVATION PROPOSED SIDE ELEVATION PROPOSED REAR ELEVATION PROPOSED SIDE ELEVATION




FRONT ELEVATION SIDE ELEVATION REAR ELEVATION SIDE ELEVATION



FLOOR PLANS



ROAD VIEW WITH ADJACENT DWELLINGS
diagramatical not to scale



SOUTH HOLLAND DC
HOUSING & PLANNING
13 SEP 1999
Ref: 0735/98

LOCATION PLAN 1-2500
REPRODUCED FROM THE ORDNANCE SURVEY MAP BY DAVID BROKER DESIGN SERVICES WITH THE SANCTION OF THE DIRECTOR GENERAL, ORDNANCE SURVEY,FOR BUSINESS USE. LICENCE No AR 375659.

HEALTH AND SAFETY C.D.M REGULATIONS 1995
THE CLIENT/DEVELOPER AND BUILDING CONTRACTOR/SUB CONTRACTOR ARE ADVISED TO AQUAINT THEMSELVES WITH THE IMPLICATIONS AND REQUIREMENTS OF THIS BUILDING PROJECT

DRAWING/FILE No 395 TB4A
DRAWING No___OF___
SCALE 1:100
DATE 02/09/99
DRAWN JL

ELEVATIONAL DETAILS
AND BLOCK PLAN

Issued / Revisions			
A	16.8.99		X B/REGS

Ref.A

ARCHITECTURAL TECHNICIANS
DANBROOKE HOUSE STATION ROAD
WISBECH ST MARY
WISBECH CAMBS.PE13 4RW


...WORK\395tb4a.dwg Plotted 1999-09-03 10:09:45

DAVID BROKER DESIGN SERVICES
2000
CONCEPT
ARCHITECTURE
COMPUTER AIDED DESIGN


CLIENT MR & MRS BISHOP
PROPOSED DWELLING HOUSE
AND GARAGE




FRONT ELEVATION




SIDE ELEVATION



REAR ELEVATION




SIDE ELEVATION



GARAGE ELEVATIONS



ROAD VIEW WITH ADJACENT DWELLINGS
diagramatical not to scale



BLOCK PLAN 1:500

SOUTH HOLLAND DC
HOUSING & PLANNING
15 JUL 1998
Ref: 0735/98

DETERMINED PLAN

LOCATION PLAN 1-2500
REPRODUCED FROM THE ORDNANCE SURVEY MAP BY DAVID BROKER DESIGN SERVICES WITH THE SANCTION OF THE DIRECTOR GENERAL, ORDNANCE SURVEY,FOR BUSINESS USE. LICENCE No AR 375659.

HEALTH AND SAFETY C.D.M REGULATIONS 1995
THE CLIENT/DEVELOPER AND BUILDING CONTRACTOR/SUB CONTRACTOR ARE ADVISED TO AQUAINT THEMSELVES WITH THE IMPLICATIONS AND REQUIREMENTS OF THIS BUILDING PROJECT

DRAWING/FILE No 395 TB4
DRAWING No 2 OF 2
SCALE 1:100
DATE 19/11/97
DRAWN GL

ELEVATIONAL DETAILS
AND BLOCK PLAN

Issued
Revisions

ARCHITECTURAL TECHNICIANS
DANBROOKE HOUSE STATION ROAD
WISBECH ST MARY
WISBECH CAMBS PE13 4RW

395TB4 Plotted: Tue Jul 14 12:01:16 1998