New dwelling
Preliminary Soft Landscape Works Schedule
(Drawing LD01)

TREES	Qnty	Spacing	(Cont / Girth) or bare root equivalent	**Unit £**	**Total £**
Acer campestre 'Elsrijk'	2	As shown	45 Ltr/12-14cm		
Prunus 'Accolade'	4	As shown	45 Ltr /12-14cm		
Tilia cordata 'Rancho'	5	As shown	45 Ltr /12-14cm		
Malus varieties	4	As shown	BR / 2Yr / 1.5-1.8m		
NATIVE HEDGING (90 lin m)					
Acer campestre – 20%	90	Dbl row at 400-500mm centres. (5 plants /per lin m)	1+2 450-600mm transplants		
Cornus sanguinea – 15%	75				
Crataegus monogyna – 20%	90				
Corylus avellana – 5%	25				
Ilex aquifolium –5%	25				
Rhamnus catharticus – 15%	75				
Viburnum opulus – 20%	90				