

NOTES

1. Do not scale this drawing.
2. All dimensions are in millimetres unless stated otherwise.
3. This drawing to be read in conjunction with all other relevant drawings and specifications.
4. All proprietary items to be installed in strict compliance with manufacturers instructions and recommendations.

STANDARD ROADS / FOOTPATH NOTES:

1. Existing structures to be broken out to minimum 450mm below top of finished surface level. Existing footpath to be broken out and rubble and existing subbase to be removed off-site.
2. Subgrade to be proof rolled with one pass of a smooth-wheeled roller having a mass per M-width of roll of not less than 2,100-kg or a Vibrating Roller having a mass per M-width of roll of not less than 700-kg or a Vibrating Plate Compactor having a mass per m2 of not less than 1400-kg. Any soft spots shall be removed and replaced with Type 1 compacted in layers not exceeding 150mm thickness.
3. All formations are to be treated with an approved herbicide before placing sib-base material on a geotextile separation membrane (Terram 1000 or similar approved)
4. All sub-base material is to be non-frost-susceptible. All concrete to be sulphate resisting

HIGHWAY WORKS NOTES

1. All works within the existing highway shall be carried out fully in accordance with the New Roads and Street Works Act 1991 and to Chapter 8 of the Traffic Signs Manual. The contractor shall provide, erect, maintain and remove upon completion all temporary signing required for works carried out within the highway. The contractor shall liaise with the Highways Authority with regard to agreeing appropriate methods of traffic management.
2. The reinstatement of the highway shall be carried out fully in accordance with the HAUC 'Specification for the Reinstatement of Openings in Highways'. Reinstatement shall be permanent (on first visit).
3. The contractor shall submit to the street works coordinator and utility companies the appropriate notices under the New Roads and Street Works Act 1991 and the Traffic Management Act. Upon completion of the works the contractor shall submit to the street works coordinator the appropriate completion notices.
5. All construction works to comply with current the Highways Authority's specifications.
6. New road markings to comply with TSRGD and the Highways Authority's specifications.
7. Construction to be in accordance with Lincolnshire County Council Highway Development Road and Sustainable Drainage Specification and Construction

P5	Details removed to reflect works required	TBP	26.06.21
P4	Sandbag Headwall detail removed	ZEK	21.04.21
Rev	Amendments	Rev'd by	Date

Client
Mr & Mrs Cross

Project
Fishergate, Sutton St. James

Title
Standard External Works
Details (Adoptable)
(Sheet 1 of 3)

Job No	20029		
Drawing No	402	Rev	P5
Status	Preliminary		
Scale	As Stated	Date	23.06.2020
Project Engineer	Drawn By	ZEK	
	Checked By	TBP	
	Approved By		



Providing engineering solutions for the Built Environment
4 Angel House, Eastgate Whittlesey,
Peterborough, PE7 1SE
07961 783825
www.parsonsengeers.co.uk

