



TF 41 NW

TYDD ST. MARY

HANNATH ROAD
(north side)

7/106
30.6.65

Greyfriars

II

House. Early C17 with mid C18 and C20 alterations. Red brick with fragments of ashlar rubble and moulded, possibly medieval, ashlar. Slate roof with C20 tiles to left hand range. Brick coped gables with kneelers and some tumbling, the main range being half hipped to the right and the projecting right hand range with rendered gable. Single projecting left gable, large ridge and lateral stacks. Some dentillation. 2 storeys, 4 bays to the main range. To the left is the single storey plus attic single bay range and to the right the projecting gabled 2 storey single bay range with lean-to projecting in the re-entrant angle. Doorway with C20 door and plain doorcase. To the left is a single segmental arched C20 tripartite glazing bar casement and to the right a single similar casement and 2 similar 2 light casements under flat heads. Further right in the side wall of the lean-to is a doorway with glazed double doors and on the far right in the gabled bay a single similar segmental arched 5 light casement. Above are 4 similar 2 light casements, to the left in the attic is a single gabled half dormer with single similar tripartite casement. To the right in the gabled bay is a single similar 3 light casement. Evidence of earlier first floor fenestration. Wall extending from lean-to has C14 pointed double chamfered arched doorway with plank door.