

LOCATION PLAN

4 PINFOLD LANE

THE OLD VICARAGE

existing private drive

Yellow hatched area is part of the existing drive to be grubbed up and become part of the garden to The Old Vicarage

covered pergola

PROPOSAL

E

F

L

G

F

L

H

L

J

K

L

existing metal gate

existing low walling

footpath

existing entrance

high road

BLOCK PLAN

LANDSCAPING: -

E- REAR AREA LAID TO GRASS.
F- TIMBER SLEEPER PLANTERS.
G- PATIO LAID WITH LIGHT COLOURED STONE (TBC).
H- LARGE TIMBER SLEEPER PLANTER TO FRONT OF BUILDING WHICH ALSO FORMS STEPS AND RAMP TO FRONT ENTRANCE.
J- SIDE GARDEN LAID TO GRASS.
K- NEW DRIVE LAID WITH LIGHT COVERED GRAVEL (TBC).
L- 2000mm GOOD GRADE TIMBER FENCING REPLACING EXISTING IF REQUIRED IN BLACK TIMBER.

MATERIALS: -

BRICKS - BLACK SMOOTH FACING BRICKS.
ROOF- NEAR BLACK METAL SHEETING.
WINDOWS - MIDNIGHT BLACK ALUMINIUM.
DOORS - MIDNIGHT BLACK GRP & ALUMINIUM.
RAINWATER GOODS - BLACK UPVC
FASCIAS & BARGEBOARDS - MIDNIGHT BLACK.
CLADDING - BLACK VERTICAL CLADDING REAL TIMBER OR FAKE.

LEGEND

- existing mains foul sewer manhole
- existing mains foul sewer drain
- proposed 300 or 450 diameter inspection chambers for foul water
- new foul water drain
- surface water soakaway crates

PROPOSED RESIDENTIAL PROPERTY ADJACENT THE OLD VICARAGE HIGH ROAD WESTON MR & MRS WALLIS

DO NOT SCALE FROM THIS DRAWING

This drawing is the property of Julian Warrick Design Consultant and is subject to copyright. The drawing is issued on the condition that it is not copied, reproduced, retained or disclosed to any unauthorised person either wholly or in part without the consent of Julian Warrick Design Consultant. No responsibility can be accepted for any errors, omissions or discrepancies arising from the use by persons other than those for which it was originally prepared. Any such persons must satisfy themselves as to the accuracy of dimensions, contours and details before proceeding. Any discrepancies are to be reported to Julian Warrick Design Consultant immediately. Figured dimensions are to be taken in preference to scaled dimensions. This drawing is to be read in conjunction with all relevant engineers drawings and specifications and any other relevant consultants drawings and specifications. All construction is to be in accordance with the Building Regulations and to the satisfaction of the Local Authority Building Control Department. The contractor is responsible for obtaining all necessary approvals and consents from the Local Authority and other bodies. The contractor is responsible for ensuring that adequate temporary bracing and propping is provided during construction. The contractor is responsible for ensuring that adequate precautions are taken during construction to comply with the Construction (Design and Management) Regulations as implemented 6th April 2007. The contractor is responsible for checking all dimensions on site before commencing any work or preparing shop drawings. Work that may not specifically be shown but that may be reasonably inferred as being necessary to complete the works shall be carried out by the contractor as if described in the contract documents. Any discrepancies are to be reported to Julian Warrick Design Consultant before proceeding with the work. Party Wall etc. Act 1996: when building or close proximity to adjoining neighbour's boundaries, Julian Warrick Design Consultant recommends that the building owner appoints a surveyor to protect his interests before any work is commenced. Where Julian Warrick Design Consultant has been employed to prepare Health and Safety information on behalf of the client, the Construction (Design and Management) Regulations 2015 place responsibilities on the client, designers and contractors. The Principal Contractor must be fully competent to plan, manage and monitor the construction work safely and without risks to health. The Principal Contractor must ensure that all persons working on the project are competent or are being supervised by competent persons. The Principal Contractor must ensure adequate welfare facilities are provided from the start to the end of the project. The Principal Contractor must prepare a construction phase plan before the construction work begins. The Principal Contractor must ensure that all workers have suitable site inductions and any further information or training needed for the work. The Principal Contractor must consult with workers regularly about matters affecting their health and safety. The Principal Contractor must report certain serious accidents, diseases and dangerous occurrences to the relevant enforcing authority. The Principal Contractor must ensure that there are suitable and sufficient welfare facilities throughout the construction work. The Principal Contractor must ensure that there are suitable and sufficient first aid facilities at all times. The Principal Contractor must ensure that everyone they employ or appoint is competent to do the tasks they are given. The Principal Contractor must not allow anyone to start work unless there are suitable arrangements in place for managing it. The Principal Contractor must ensure that there is a suitable and sufficient management system in place for the work and that it is followed.

-						
-						
-						

BLOCK & LOCATION PLANS

1/100 1/2500 AT A1	24/5/25

J195-PL 9

Julian Warrick
Architectural Design Consultant

Email: julian@jwarrick-design-cons.com
Tel: 01775 820123
Mob: 07849 652067
Houzz.co.uk

8 Beech Grove
Donington
Spalding
Lincs
PE11 4XQ