



North West Elevation



Location Plan 1:2500




Block Plan 1:500

PITCHED ROOF CONSTRUCTION.
Interlocking concrete roof tiles to match existing to B.S.473:550 part 2 1971. on 25 x 38 softwood treated battens on underfelt to B.S 747 (type 1F) and in all cases to be lapped by 150mm both vertically and horizontally. Tiles to be laid with min. headlap of 75mm and to be fixed in accordance with regard to wind speed, roof pitch and exposure category as detailed in CP3 chapter V part 2 1972. Twinaplate specialist made prefabricated roof trusses to comply with B.S. 5268 part 3 1985. Trusses to be King Post type at 600c/c to a pitch of 30 deg. 38 x 100 ridge node binder 38 x 100 ceiling binders: All trusses to be strapped to wall plate by 30 x 5 galvanised metal straps acting as anchor and lateral restraint straps at max. 1.5m c/c. Note: provide solid bridging beneath straps: 90 x 100 wall plate bedded on sand and cement: 25 x 175 fascia boards: 6mm ext. grade plywood soffit complete with 10mm wide continuous air gap and fly proof screen: All structural timber to be min. SC3 grade: At roof intersections provide 25 x100 lay boards and diminishing trusses at 600 c/c: Install code 4 lead valley liner. Close cavity at plate level.


CEILINGS.
150mm glassfibre insulation laid between joists: 12.7mm Gyproc "duplex" plasterboard 3mm skim finish: Provide min 38 x 38 noggins to all plasterboard edges. All joints to be taped and filled: Provide access trap to roof space: opening to be lined with 25 x 25 planted stops: Access panel to be 12mm ply with layer of 12.7mm Fireline board fixed to face.

WALLING.
265 cavity walling to consist of face brickwork to B.S.3921:1974 for clay bricks and B.S. 187:1978 for calcium silicate bricks: 65 cavity: build into cavity Rockwool cavity wall batts insulation boarding in accord. with makers instructions and agrement cert' No.83/1087 . 100mm Tarmac Hemelite solid insulation blocks or similar: Cavity walls tied together using galvanised iron twist ties set 900 horizontally and 450 vertically to B.S. 1243:1978 wall ties positioned at 300 vertical centres at all unbonded closures of cavity: Close cavities with 'Thermabate' preformed closerand provide bitumen felt DPC to C.P.121: External walls to have max 'U' value of 0.45 W/m2 deg. C.: Internal wall of 215 face brickwork and to receive 10mm S/C render and 3mm skim (except Conservatory).

SUB STRUCTURE WALLING.
100/215mm class A dense concrete blocks: DPC to external wall positioned in accordance with CP 102 min. 150 above finished ground level: Weak mix concrete infill to base of cavity no closer than 225 to DPC. All brickwork below D.P.C. to be F.L. quality.



North East Elevation.



South West Elevation

FOUL DRAINAGE.
Inspection chamber construction to be 'Osma'' and installed in accordance with makers instructions with the internal diameter related to the depth in accordance with B.S.8301:1985 Foul drainage pipes to be 100mm dia. UPVC. to B.S.4660:1983 Flexibly jointed and laid to makers instruction to a fall of 1:70 bed and surround with 100mm pea gravel: Where pipes pass under floors encase in 150mm pea gravel: Where pipes pass under drives surround in 150mm concrete with flexel joints to correspond with joints in pipework Provide 65 x 100 prestressed concrete lintol bridging where pipes pass through walls, allow 50mm gap around pipe, opening masked both sides of wall with ridged sheet material: Soil and vent pipes to be 100mm int. dia. PVC to B.S.4514: 1983 and to be fitted with air addmittance valve. Waste pipes to be 40mm. dia. PVC to B.S.3943:1979 complete with rodding eyes at every change in direction: Basin and sink to have 75 deep seal traps.

SURFACE WATER DRAINAGE.
115 dia. Squareline rainwater gutters to 83 sq. rainwater pipes 82.4 dia. underground pipes flexibly jointed to a fall of 1:70 pipes bedded and surrounded in 100 pea gravel and discharge to 1.2m dia. soakaway min. 5.0m from dwelling.

GLAZING.
Double glaze extension throughout. All Glazing between f.f.l and 800mm high and between f.f.l. and 1500mm high in doors and side lights to be safety glass to B.S. 6206.


VENTILATION
All windows to have opening lights to give the equivalent of 1/20th the floor area. Window hands to be fitted with hit and miss ventilators to give min 8000msq permanent free air ventilation per habitable room.

GROUND FLOOR CONSTRUCTION.
Strip all vegetable soil and lay floor as follows: 50mm sand and cement screed on 100 concrete oversite: Concrete mix ST3 to B.S. 5328 1990: 50mm Polystyrene insulation boardon 1200g polythene D.P.M. lapped continuous with D.P.C by 100mm: 150 blinded and consolidated hardcore.


FOUNDATIONS.
Under walls as shown provide strip concrete foundations 225 x 600 all ST3 mix to P.S. 5328 1990. All foundations taken down to bear on load bearing strata min. depth of 600 to top of foundations: should shrinkable soil conditions be found on site then foundations shall be taken down to a depth of 1 metre below ground level.

LINTELS.
All lintels to be as manufactured by messrs I.G and to be installed in accordance with makers instructions. And to have min. end bearing of 150mm and at external positions to have cavity tray d.p.c to CP.121: Internal lintels to be I.G. 100 Box type.


Plan Existing



Section A-A



Section B-B



Plan Proposed.

HOT WATER AND SPACE HEATING
Extend existing hot water system. All hot water storage tanks and pipework to be insulated to B.S.L1 part 3.

DETERMINED PLAN

Notes & Schedules

SOUTH HOLLAND DC
HOUSING & PLANNING
31 JUL 1995
Ref: 0795/95

CONTRACTOR TO CHECK ALL DIMENSIONS ON SITE BEFORE WORK COMMENCES
COPYRIGHT RESERVED

revision	date	init	revision details

COOPER ARCHITECTURAL DESIGN
BRONAVON, HOCKLESGATE
FLEET, SPALDING, LINCS. PE12 8LY
TEL: 0406 422742

client
MR & MRS M. BOWERS

project
PROPOSED EXTENSION TO BUNGALOW.
87 BROADGATE,
WESTON,
SPALDING,
LINCS.

drawing

scale 1:50 1:100

drawing no. 95001

date JULY '95

drawn

SUMMIT D.O.S 941079