(C)2003 WALDECK ASSOCIATES LTD.

FOUL SEWER DETAILS

MH No. / CO-ORDS	COVER LEVEL	CONNECTS	INVERTS		PIPE DIA.	MH DIA.	TYPE: MANHOLE	TYPE: COVER
F1	2.859	0	0	2.150	150	1350	TYPE F	D400
F2	2.946	1 0	1	1.790	150	1350	TYPE F	D400
			0	1.790	150			
F3	2.805	1 0	1	1.512	150	1350	TYPE F	D400
			0	1.512	150			
F4	2.982	1 0	1	1.297	150	1350	TYPE F	D400
			0	1.297	150			
F5	2.839	1 0	1	1.065	150	1350	TYPE F	D400
			0	1.065	150			
EXFMH6 EXISTING	3.070	1-BD EX1 EX0	1	0.998 BACK DROP	150			
			EX1	0.080	150			
			EX0	0.080	150			

STORM SEWER DETAILS

MH No. / CO-ORDS	COVER LEVEL	CONNECTS	INVERTS		PIPE DIA.	MH DIA.	TYPE: MANHOLE	TYPE: COVER
S1	2.950	0	0	2.049	150	1050	TYPE B	D400
S2	3.095	1 0	1	1.914	150	1350	TYPE B	D400
			0	1.914	375			
S3	2.938	1 0	1	1.804	375	1350	TYPE B	D400
			0	1.804	375			
S4	2.807	1 0	1	1.731	375	1350	TYPE B	D400
			0	1.731	375			
S5	2.974	1 0	1	1.625	375	1350	TYPE B	D400
			0	1.625	375			
S6	2.808	1 0	1	1.533	375	1350	TYPE B	D400
			0	1.533	375			
S7	2.595	1 0	1	1.397	375	1350	TYPE B	D400
			0	1.397	375			
S8	2.680	1 0	1	1.100	375	1350	TYPE B	D400
			0	1.100	375			
S9	2.740	1 0	1	0.803	375	1350	TYPE B	D400
			0	0.803	375			
S10	2.705	1 0	1	0.506	375	1350	TYPE B	D400
			0	0.506	375			
S11		1 OUTFALL	1	0.400	375			

NOTES

1. DO NOT SCALE THIS DRAWING.
2. ALL DIMENSIONS ARE IN MILLIMETERS UNLESS STATED OTHERWISE.
3. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL OTHER RELEVANT DRAWINGS.
4. ALL PROPRIETARY ITEMS ARE TO BE INSTALLED IN STRICT COMPLIANCE WITH THE MANUFACTURES INSTRUCTIONS AND RECOMMENDATIONS.
5. PROVIDE CONCRETE SURROUND TO ALL PIPEWORK, WHERE 1.2m OF COVER TO TOP OF PIPE BARREL IS NOT ACHIEVABLE.
6. BRANCH AND ANCILLARY CONNECTIONS TO BE 150mm DIA LAID AT GRADIENTS BETWEEN 1:10 AND 1:80.
7. GULLY CONNECTIONS TO BE 150mm DIA. LAID AT GRADIENTS OF AT LEAST 1:150 UNLESS OTHERWISE STATED.
8. ALL PIPEWORK TO BE LAID WITH LEVEL SOFFITS UNLESS OTHERWISE STATED.
9. ALL FOUL PIPES TO BE 150Ø AT A GRADIENT OF 1:150 UNLESS OTHERWISE STATED.
10. NO WORKS SHALL COMMENCE ON SITE UNTIL APPROVAL HAS BEEN OBTAINED FROM LCC, AWS AND ALL OTHER RELEVANT AGENCIES/AUTHORITIES.
11. THE SPECIFICATION IN ALL RESPECTS SHALL BE IN ACCORDANCE WITH THE CURRENT 'LINCOLNSHIRE DESIGN GUIDE FOR RESIDENTIAL AREAS' AND 'DEVELOPMENT ROAD SPECIFICATION AND CONSTRUCTION' PUBLICATIONS IN FORCE ON THE COUNTY AT THE TIME OF CONSTRUCTION.
12. ALL SEWERS ARE TO BE CONSTRUCTED IN ACCORDANCE WITH THE PROCEDURES AND SPECIFICATIONS CONTAINED IN "SEWERS FOR ADOPTION" (5th Edition - July 2001).

RECEIVED
- 1 AUG 2003

RECEIVED
- 7 AUG 2003
0979/03

Rev.	Amendments	Rev'd By	Date

Client
CB DESIGN GROUP

Project
PROPOSED DEVELOPMENT, BROADGATE, WESTON HILLS, SPALDING

Title
PROPOSED MANHOLE SCHEDULES

Job No **33376**

Drawing No **33376/A1/04**

Status **PRELIMINARY**

Scale **N/A** | Date **JUL 03**

Project Engineer **PW** | Drawn By SO | Checked By

Waldeck Associates
Consulting Civil & Structural Engineers
Kesteven Business Centre,
2 Kesteven Street,
Sleaford,
Lincolnshire,
NG34 7DT
Tel: 01529 415909
Fax: 01529 414844
E-mail: eng@waldecks.freeserve.co.uk