

NOTES

This drawing is the property of FPCR Environment and Design Ltd and is issued on the condition it is not reproduced, retained or disclosed to any unauthorised person, either wholly or in part without written consent of FPCR Environment and Design Ltd.

Ordnance Survey base mapping - supplied by client.

0 10 20 30 40m

N

KEY

- Site Boundary
- Trees
- Native Mixed Hedgerow (planted double staggered, 5 plants lin/m)
- Amenity Grassland (to be Naturescape NL4 'Hardwearing Lawn Mixture' or similar approved)
- Flowering Lawn Grassland (to be Naturescape N14 'Flowering Lawn Mixture' or similar approved)
- Flowering Meadow Grassland (to be Naturescape N1 'General Purpose Meadow Mixture' or similar approved)
- Reed Beds

NOTES:

- Scrub planting to be set out at 2 plants per sq/m. Species to be set out in groups of 3,5 or 7 plants and randomised to avoid patterns. All whip planting to be staked and protected with a shrub shelter (Tubex or similar approved)

- Mixed Native hedgerows to be planted double staggered, 5 plants lin/m. All whip planting to be staked and protected with a shrub shelter (Tubex or similar approved)

- All proposed standard trees to be double staked. Multi stem trees to be underground guyed.

- For planting schedule see 9420-L-01.

rev	date	description	drn / chkd
B	07.04.2021	Updated Layout	SRE / DH
A	18.01.2021	Amendments based on comments	TW / DH
-	15.01.2021	First Issue	TW / DH

masterplanning
environmental assessment
landscape design
urban design
ecology
architecture
arboriculture

FPCR Environment and Design Ltd
Lockington Hall
Lockington
Derby
DE74 2RH

t: 01509 672772
e: mail@fpcr.co.uk
w: www.fpcr.co.uk

client
Persimmon Homes

project
Weston, Spalding, Lincolnshire

drawing title
POS LANDSCAPE PROPOSALS (Sheet 2 of 2)

scale	drawn / checked	revision date
1:500 @ A1	TW / DH	7 April 2021

drawing number
9420-L-02

rev
B

File: K:\9400\9420\LANDS\Plans\9420-L-01-06B Landscape Proposals.vwx