

Materials

BRICKS:	Vandersanden Handmade Flemish Antique (Details enclosed.)
ROOF TILES:	Double Roman. Smooth Brown. Wienerberger or similar approved. (Details enclosed.)
GUTTERS & DOWNPIPES:	Black UPVC. Downpipes 68 mm round section. Gutters 112mm half round section.
WINDOWS:	UPVC Flush casement windows. Anthracite (Details enclosed.)
FRONT DOOR	Composite door. Colour to clients choice. Style as application details.

Facing Bricks



Product Information

Dimensions: tolerance category	T2	
Dimensions: range category	R1	
Active soluble salt	S2	
Average compressive strength	$\geq 20 \text{ N/mm}^2$	Tested to the bed face
Normalised compressive strength	$\geq 20 \text{ N/mm}^2$	Tested to the bed face
Dimensional stability	NPD	
Bond Strength general	NPD	Value according EN998-2 Annex C
Adhesive strength (mortar)	NPD	Value according EN998-2 Annex C
Reaction to fire	A1	Category
Water absorption	$\leq 14\% \text{ m/md}$	
Water vapour permeability	5/10	
Net dry density	$1740 \text{ kg/m}^3 \text{ (D1)}$	
Gross dry density	$1630 \text{ kg/m}^3 \text{ (D1)}$	
Equivalent thermal conductivity	$\leq 0,60 \text{ W/m.K}$	Value according EN1745, Annex A 50%
Freeze/thaw resistance	F2	
Dangerous substances	NL-BSB	According Annex ZA.3

VANDERSANDEN HANDMADE FLEMISH ANTIQUE

Roofing Slates



SPANISH NATURAL ROOF SLATE. 500mm x 250mm Preholed.

UPVC Flush Casement Window



The colour is ANTHRACITE