

ROOF CONSTRUCTION.

WALLS

FLOOR
50 sand/cement screed on 100 concrete sub-
floor C20P on 1000 gauge DPM on 150 blinding
and compacted hardcore. DPM to be made
continuous with DPC in walls.

Thicken floor slab to 250x450 wide below non-loadbearing partition walls.
Foundations taken down to suitable load bearing strata, determined on site with local authority Building Inspector. 750 min' below ground level, if shrinkable sub-soil is found on site, foundations to be 1000 below finished ground level.

RAINWATER DISPOSAL. PVC rainwater goods. 100 N.R. gutters @ 8' down pipes to 100 @ uPVC drains to 1m' brick rubble soakaways sited at least 3m from any buildings.

LINTELS
I.G. steel lintels to all door & window openings as detailed, installed to manufacturers specification. (150 min' and bearing)

FOOTPATHS
800 wide concrete footpaths with 75 fall away from dwelling. 100 blinded and well consolidated hardcore base.

GRAVEL DRIVE.
75 of 19 down washed gravel on 100
consolidated hardcore, 50x150 precast
concrete edging kerbs, bedded and haunched
in weak mix concrete.

9.3.34. ADDITIONAL STORAGE IN GARAGE APPLICATION.
9.3.34. CONTINUATION WITHOUT COMPLAINT WITH CDDT.
9.3.34. ADDITIONAL TREE PLANTING.
2.6.34. CONDITION COMPLIANCE.
9.3.34. CHANGE OF USE APPLICATION.
18.1.33. K3. SECTION 12.211 SURF..
14.4.33. BRIDGE IMPROVEMENTS
2.1.33. RE-POSTING FRUIT SHOP -
EVIDENCE LENGTH BY 300MM.

G. R. MERCHANT
I.ENG AMICE, FAWO,
ARCHITECTURAL, STRUCTURAL
& LAND DRAINAGE CONSULTANT
TEL: HOLBEACH (0406) ~~670000~~ 490800

PROJECT:

FRUIT STORE (CHANGE OF USE).
MIDDLE ROAD.
WHAPLODE.

CLIENT:
R.B. MAYER.
"KAR WAYNE".
MALTEN LANE.
WHADLODE.

SCALES: $1/100 \pm 1/50$	DATE: 7-1-1980
-----------------------------	-------------------

(UNLESS OTHERWISE STATED)	
G. R. MERCHANT.	DRAWING No.: RBM. 1K.

REVISIONS:
* B C D E F G H V K

ROOF PLAN

PLAN

HEATING BY ELECTRIC
NIGHT STORAGE / ECONOMY 7

SECTION AA

AMENDED PLAN
Ref.

SOUTH HAVENLAND D.C.
PLAN DEPT
20 OCT 1994
REF. H23/0000/94
DL01

LOCATION PLAN
SCALE: 1/2500

**DETERMINED
PLAN**

K.15.10.94 Amend to 5/1/95