

Project:	Drg. Title:	Client:	Job No.: 031601		**ANDREW M WRIGHT LTD**
High Road, Whaplode	Schedule of Materials	Haycroft Homes Ltd	Drg. No.: PD12	Rev.: P4	CHARTERED ARCHITECT

Location	Type	Product	Colour	Image
Walls (Plots 9, 19, 21, 22, 24, 25, 28, 29, 30 & 32) as indicated on drawing PD05(P3)	Facing brickwork	Old Saxon Blend	Red	
Walls (Plots 10, 12, 14, 18, 23, 26 & 27) as indicated on drawing PD05(P3)	Facing brickwork	Old Hambleton	Red	
Walls (Plots 1-8, 11, 13, 15-17, 20, 31 & 33) as indicated on drawing PD05(P3)	Facing brickwork	Abbey Reserve	Red	
Stone effect cills (To all windows set within facing brickwork only).	Reconstituted stone	Stone effect cill	Cream	

Walls – Soldier courses above windows/doors, corbelling, low level brickwork up to 0.45m above FFL (Plots 10, 12, 14, 18, 20, 23, & 26/27)	Facing brickwork - details	Blue brick	Blue	
Walls – Soldier courses above windows/doors, corbelling, low level brickwork up to 0.45m above FFL (Plots 1, 2, 9, 11, 13, 15-17, 19, 21, 22, 24/25, 28/29, 30/31, 32 & 33)	Facing brickwork - details	Red Brick	Red	
Walls – Cladding Dormers - Cladding (Plots 3-6, 9-14 & 18-23)	Timber effect weatherboarding	Marley Cedral Lap Weatherboard (or equivalent)	Black	
Roofs (Plots 8, 7, 9, 10, 12, 14, 18, 20, 23, 26 & 27) as indicated on drawing PD05(P2)	Slate effect interlocking slate	Marley Edgemere	Smooth grey	

Roofs (Plots 1-6, 9, 11, 13, 15-17, 19, 21, 22, 24, 25, 28-33) as indicated on drawing PD05(P2) (Porches only of Plots 10, 12, 14, 18, 20 & 23) as indicated on drawing PD05(P2)	Concrete interlocking tile	Redland Fenland Pantile	Farmhouse red	
Windows (Plots 9, 11, 13, 19, 21 & 22)	Upvc or timber	Window frame	Grey	
Windows (Plots 1-8, 10, 12, 14-18, 20 & 23-33)	Upvc or timber	Window frame	White or cream	
Doors (front)	Composite timber effect or timber	Cottage style doors. Styles to vary.	Colours to vary	