



Re: Planning Permission H23-0508-16

Reference condition 15

Precautions to prevent the deposit of mud off the public highway will entail:

1. Provision of temporary roadways and keeping vehicle movements to these whilst roads are under construction.
2. All vehicles leaving the site must have their wheels cleaned using a water supply and jet wash at the site entrance to remove any surplus mud to prevent the contamination of the roads during the initial construction stage of the roads.
3. Where any mud is deposited on the public highway suitable cleaning arrangements (e.g. use of mechanical road sweeper) will be made as soon as practicably possible.
4. Once the initial 60 metres of road is constructed to binder course, keeping this clean therefore not allowing any migration of mud onto the highway.

Derek Ford
Director