

Installation Type	Unit of Measure	Capacity/Flow rate (1)	Use Factor (2)	Fixed use (litres/person/day) (3)	Litres/person/day = [(1)x(2)] + (3) (4)
WC (single flush)	Flush Volume (litres)		4.42	0.00	0
WC (dual flush)	Full flush Volume (litres)	6	1.46	0.00	8.76
	Part flush Volume (litres)	4	2.96	0.00	11.84
WC (multiple fittings)	Average effective flushing Volume (litres)		4.42	0.00	0
Taps (excluding kitchen/utility room taps)	Flow rate (litres/min)	5.00	1.58	1.58	9.48
Bath (where shower also present)	Capacity to overflow(litres)	210.00	0.11	0.00	23.10
Shower (where bath also present)	Flow Rate(litres / minute)	6.15	4.37	0.00	26.88
Bath Only	Capacity to overflow(litres)		0.50	0.00	0
Shower Only	Flow Rate (litres/minute)		5.60	0.00	0
Kitchen/Utility room sink taps	Flow rate (litres/minute)	6.18	0.44	10.36	13.08
Washing Machine	(Litres/kg dry load)	8.17	2.1	0.00	17.157
Dishwasher	(Litres/place setting)	0.84	3.6	0.00	3.02
Waste disposal unit	(Litres/use)	☐ Present	3.08	0.00	0
Water Softener	(Litres/person/day)		1.00	0.00	0
	(5)	Total Calculated use (litres/person/day) =SUM(column 4)			113.32
	(6)	Contribution from greywater (litres/person/day)			0
	(7)	Contribution from rainwater (litres/person/day)			0
	(8)	Normalisation factor			0.91
	(9)	Total internal water consumption = [(5)-(6)-(7)]x(8) (litres/person/day)			103.12
	(10)	External water use			5.0
	(11)	Total water consumption (Building Regulation 17.K) =(9)+(10)(litres/person/day)			108.1

Installation Type	Make/Model (mandatory)	Litres/Person/Day
WC (dual flush)	Ideal Standard Eurovit+	20.6
Taps	Hansgrohe Vernis	9.48
Baths (shower(s) present)	Milan shower bath, Orchard Derwent thermostatic shower	22.00
Showers (bath(s) present)	Orchard Derwent	26.88
Kitchen Taps	Caple Lamar	13.08
Washing Machines		17.157
Dishwasher	Lamona 60cm integrated	3.02



©Water Research Centre Limited 2024

[Terms and Conditions](#)
[System Requirements](#)