

Drove Road Planting Schedule



Maintenance Plan

Hedging	Feeding	Watering	Trimming	Weeding
Carpinus betulus (Hedge 1.8m)	Feed hedges in early spring with all purpose, organic fertiliser in to assist healthy growth. In late winter feed with Bonemeal to provide slow releasing nutrients in the lead up to spring. Fork in well after application	During first year apply 5 litres of water per meter of hedging at least twice a week. Water on an evening or when cloudy to ensure minimum evaporation.	Trim once a year in mid to late summer	Remove and/or prevent weeds and grass from encroaching onto new plants. Weed by hand
Carpinus betulus (Hedge 1m)			Trim once a year in mid to late summer	
Prunus lusitanica			Light trim in late summer and remove any damaged or congested shoots	
Hedging	Feeding	Watering	Trimming	Weeding
Carpinus betulus	Add a 50mm depth of Bark mulch around the base of the tree. This should ideally cover the entire root area and ensure mulch is topped up twice a year	Trees planted from November to March will require no watering during these months. Water the trees for the first 2 years during the growing seasons April - October. During the height of summer these will need 20 litres every other day	Pruning will occasionally be necessary to remove dead or diseased branches	Remove and/or prevent weeds and grass from encroaching onto new trees. Weed by hand
Photinia 'Red Robin' Tree				
Koelreuteria paniculata				
Amelanchier x grandiflora - 'Robin Hill'				
Corylus colurna				

Notes and comments:

The scheduled size indicates our preferred size at the time the planting plan was created. This may change due to onsite soil conditions, plant availability and seasonality, and any alterations in price will be reflected in your final quotation.

The circular plant symbols show the eventual size of the plants at maturity and where possible reflect flower colour or evergreens.

Notes

Revision: Date: 00.00.00
Rev Notes:

Project Title: Drove Road Planting Schedule



Sqm Overall: N/A

Checked By: ML

Drawn By: PLR
Date: Sept 2019

Scale: 1/200 @ A2
Drawing No: 1

Drawing Status:
For Planning

Planting schedule for Drove Road

Hedges	Supplied Height	Eventual Height	Method of supply	Quantity	Density planted at	Pot size	Time of supply/planting
Carpinus betulus (Hedge 1.8m)	1.8m	Maintained at 1.8m high	Containerised	268	6 plants per LM	N/A	Mar - Nov
Carpinus betulus (Hedge 1m)	1m	Maintained at 1.2m high	Containerised	228	9 plants per LM	N/A	Mar - Nov
Prunus lusitanica	30/40cm	Maintained at 60cm high	Containerised	91	4 plants per LM	2L	Mar - Nov
Trees	Approx. Supplied Height	Eventual Height	Method of supply	Quantity	Density planted at	Pot size	Time of supply/planting
Carpinus betulus	4/5m high	20 meters +	Containerised	3	Specified points throughout borders	65L/100L	Mar - Nov
Photinia 'Red Robin' Tree	3/4m high	4-7 meters high	Containerised	2	Specified points throughout borders	35L, 45L, 55L or 65L	Mar - Nov
Koelreuteria paniculata	3/4m high	7-12 meters high	Containerised	6	Specified points throughout borders	35L, 45L, 55L or 65L	Mar - Nov
Amelanchier x grandiflora - 'Robin Hill'	3/4m high	3-5 meters high	Containerised	5	Specified points throughout borders	35L, 45L, 55L or 65L	Mar - Nov
Corylus colurna	3/4m high	7-12 meters high	Containerised	2	Specified points throughout borders	35L, 45L, 55L or 65L	Mar - Nov

Bestall & Co, The Garden Design Studio, The Stables Courtyard, Renishaw Hall, Nr Sheffield, S21 3WB

E - hello@bestall.co
T - 01246439340
www.bestall.co.uk

BESTALL
& CO