The specification in all respects shall be the current "Lincolnshire Design Guide For Residential Areas" and "Development Road Specification" publications in force in the County at the time of construction.

KEY

Storm sewer:
Foul sewer:
Storm drain: (Invert Level)
Foul drain: (Invert Level)
Street light:

To L.C.C. Spec. Section 14 "Development Road Specification and Construction"

ROAD LIGHTING KEY:

- 6m TYPE 3M10 COLUMN WITH POST TOP MOUNTED LANTERN TO APP 14/2 (WRTL IRIS 55w OR EQUIVALENT)
- 6m TYPE 3M10 COLUMN WITH POST TOP MOUNTED LANTERN TO APP 14/2 (PHILIPS FG5224 35w OR EQUIVALENT)
- DL DISTRICT LANTERN TO BE DISCONNECTED AND TAKEN TO TIP. S.H.D.C. TO BE INFORMED.
- RAL 6m TYPE 3M10 RAISE & LOWER COLUMN WITH POST TOP MOUNTED LANTERN TO APP 14/2 (WRTL PATHFINDER 42w OR EQUIVALENT)
- PROVISIONAL DUCTING TO ACCOMMODATE P.E.S. CABLE FEED. (50mm DIA.BLACK)

N.B. THE CONTRACTOR IS MADE AWARE OF RELATED S.H.W APPENDICES AND RELEVANT CORRESPONDENCE ON THIS DEVELOPMENT

STREET LIGHTING DESIGN: WHAPLODE, STOCKWELL GATE
DESIGNER: J.D. ROBSON
SCHEME NO.: 305551/01P
DATE: MAR 03

G		
F	28/7/03	STREET LIGHTING SCHEME CORRECTED
E	JULY 03	REVISIONS CLOUDED.
D	23/04/03	Notes revised.
C	20/09/93	Rd 1 f/w revised ch 60. Bellmouth notes revised. Street lighting & road marking notes & details added.
B	17/07/93	Positions of F12 & F13 amended.
A	16/03/93	Sewers redesigned, additional information added.

Revisions

Project: STOCKWELL GATE, WHAPLODE, LINCOLNSHIRE

Title: ROAD & SEWER LAYOUT SHEET 1 OF 2

Client: ASHWOOD HOMES

13 SEP 2003

Architect: John Finch Partnership

Scales: 1/200 | Date: February 1993

Drawn: GDS | Checked: | Reinf. | Checked:

RLT Engineering Consultants Ltd.
CONSULTING STRUCTURAL & CIVIL ENGINEERS
RLT House 5 Oxford Road Colchester Essex CO3 3HN
Telephone: 0206 768655 Fax: 0206 768656

Drawing No. 9112/04/01