



JOINERY / LINTEL SCHEDULE			
ALL JOINERY CODES ARE "BOLD-WEN" JOINERY			
POSTN	JOINERY	LINTEL	LENGTH
1	ROR35/ H113C - SHALLOW CIRCULAR BAY	LG. LI/ 575	2100
2	FCP120 - FRENCH DOORS	LG. LI/ HD75	3900
3	PURPOSE MADE SCREEN	LG. LI/ 575	1500
4	FCP120 - FRENCH DOORS	LG. LI/ HD75	2100
5	H312CL - WINDOW	LG. LI/ HD75	1200
6	PN29H - EXTERNAL DOOR	LG. LI/ HD75	2100
7	H310CC - WINDOW	EXISTING	-
8	H110C - WINDOW	LG. LI/ 575	1800
9	REMOVE WINDOW - FORM OPENING	2025mm x 2025mm x 46 kg/ m LC	4700 - see design sheet
10	FORM OPENING	-	-
11	H209C - DORMER WINDOW	LG. LI/ HD75	2400
12	FORM OPENING	LG. LI/ 575	1050
12a	H110C - WINDOW	LG. LI/ HD75	2100
13	H312CL - WINDOW	LG. LI/ HD30	1500
14	H212C - WINDOW	LG. LI/ 575	2400
15	REMOVE WINDOW - FORM OPENING	LG. LI/ 575	1200
16	INTERNAL DOOR		

SUPERSEDED

1239/08

**DETERMINED
PLAN**

E.	CLIENTS REAR & INTERVAL ALTERATIONS.	NOV '06
D.	BUILDING REGULATIONS AMENDMENTS.	AUGUST '07
C.	BUILDING REGULATIONS APPLICATION.	AUGUST '07
B.	CLIENTS AMENDMENTS.	MAY '07
A.	AMENDMENTS-SITE MEETING WITH PLANNING OFFICER.	MAY '07

G. R. MERCHANT LTD.
I.ENG AMICE FIWO
**ARCHITECTURAL, STRUCTURAL
AND LAND DRAINAGE
CONSULTANTS**
4 Wrights Mews
12A Park Road, Holbeach,
Spalding, Lincs. PE12 7XE
Tel 01408 486000
Fax 01408 428744
E-Mail: gr.merchant@btconnect.com

Project
EXTENSIONS, ALTERATIONS
HOLLY COTTAGE,
ROMAN BANK, SARACENS HEAD,
SPALDING. LINC'S. PE12 8BB.

Client
M. PHIPPS & B. SPECKMAN.

Drawing

FLOOR PLANS & ELEVATIONS - PROPOSED

Job Ref.	Drawing No.
1470-06	05F

Date	Drawn
MAY '07	ARM

Scales	1/50, 1/100,
--------	--------------

DO NOT SCALE FROM THIS DRAWING

The drawing is prepared and issued for the use of the contractor only. It is not to be used for any other purpose than that for which it was prepared. The contractor is responsible for the accuracy of the drawing and for the results of any work done therefrom. The contractor is not to be held responsible for any errors or omissions in the drawing or for any work done therefrom. The contractor is not to be held responsible for any work done therefrom. The contractor is not to be held responsible for any work done therefrom.